ROUTE: Richards St. (5th Ave. to S/O Colburn Ave.) - Jointed PCC — PATCHING = CLASS B

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
5th Ave.	I-80	SB	1	12	6	72	8
			2	12	6	72	8
			1	12	8	96	11
			1	12	6	72	8
			1	12	8	96	11
			1	12	6	72	8
			2	12	6	72	8
			1	12	25	300	33
			2	12	25	300	33
			1	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	15	180	20
			2	12	25	300	33
			1	12	10	120	13
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
I-80	Colburn		1	12	6	72	8
			2	12	6	72	8
			LT	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			LT	12	10	120	13
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			3	20	6	120	13
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			3	12	6	72	8
			1	12	6	72	8

ROUTE: Richards St. (5th Ave. to S/O Colburn Ave.) - Jointed PCC — PATCHING = CLASS B

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	12	144	16
			1	12	6	72	8
			2	12	8	96	11
Cont I-80	s/o Colburn	SB	1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			1	12	6	72	8
			1	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	12	144	16
			1	12	8	96	11
			1	12	6	72	8
			2	12	6	72	8
			2	12	8	96	11
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
		LT. Lane	1	9	6	54	6
		Narrows	2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	12	144	16
s/o Colburn	I-80	NB	1	12	6	72	8
			2	12	6	72	8
			1	12	15	180	20
			2	12	15	180	20
			1	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8

CONTINUED ON NEXT SHEET

FILE NAME = c:\pw_work\PWIDOT\WILGREENDP\d0183633\Design.dgn	USER NAME = wilgreendp	DESIGNED -	REVISED - 4/28/10 - DW
	PLOT SCALE = 100.0000 ' / IN.	DRAWN -	REVISED -
	PLOT DATE = 4/28/2010	CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
RICHARDS ST.

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2010-016PP	WILL	19	6
		CONTRACT NO. 60K35		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

Design.dgn 4/28/2010 10:59:51 AM User=wilgreendp