

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	2222.3B	COOK	77	7
STA. 12+06.00		TO STA. 16+17.11		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

PROJECT LOCATION: FAI 57 AT GENOA AVENUE  
COOK COUNTY

CODE NUMBER	ITEM	UNIT	100% STATE			
			TOTAL QUANTITY URBAN	ROADWAY 1000-2A	BRIDGE X271-2A	LIGHTING Y030-1E
* 87900200	DRILL EXISTING HANDHOLE	EACH	4			4
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103	103		
X0323080	DRAINAGE SCUPPERS, DS-12	EACH	4		4	
* X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	6			6
X0323859	DOWNSPOUT CONNECTION	EACH	2	2		
* X0324198	REMOVAL OF ASBESTOS CEMENT CONDUIT	FOOT	1,148		1148	
* X0324302	REMOVAL OF TEMPORARY LIGHTING FIXTURE, SALVAGE	EACH	12			12
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	50		50	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	464		464	
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	2777	2777		
X0325837	WET REFLECTIVE TEMPORARY TAPE TYPE III, 6 INCH	FOOT	820	820		
X0325840	WET REFLECTIVE TEMPORARY TAPE TYPE III, 12 INCH	FOOT	353	353		
X0325841	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	119	119		
X0325842	WET REFLECTIVE TEMPORARY TAPE, TYPE III, LETTERS AND SYMBOLS	SQ FT	337	337		
* X0326323	UNDERPASS LUMINAIRE, 70 WATT, HIGH PRESSURE SODIUM VAPOR, STAINLESS STEEL HOUSING	EACH	8			8
* X0326328	STREET LIGHTING CABLE, 1/C NO. 6, CITY OF CHICAGO STANDARD	FOOT	1262			1262
* X0326329	STREET LIGHTING CABLE, 1/C NO. 8, CITY OF CHICAGO STANDARD	FOOT	631			631
* X0329887	INSTALL LIGHT POLE MAST ARM & LUMINAIRE (MATERIAL PROVIDED BY THE CITY OF CHICAGO)	EACH	8			8
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1		
X280050	INLET FILTER CLEANING	EACH	12	12		
Z0011400	COLD MILLING EXISTING MEDIAN	SQ YD	33	33		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	6	6		
Z0018800	DRAINAGE SYSTEM	L SUM	1		1	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	2	2		
Z0030320	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 2	EACH	2	2		
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1		
X8210030	TEMPORARY UNDERPASS LUMINAIRE, 70WATT, HIGH PRESSURE SODIUM VAPOR, STAINLESS STEEL HOUSING (INSTALL ONLY)	EACH	12			12

\* SPECIALTY ITEM

PLOT DATE = Monday, March 09, 2010  
FILE NAME = S:\1-CADD\11-11\11-11-07-988-egdl.dgn  
PLOT SCALE = 50%  
USER NAME = 3696



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
SHEET 4 OF 4  
**GENOA AVENUE OVER FAI-57**

SCALE: VERT. NONE  
HORIZ.  
DATE: 3/1/2010

DRAWN BY: E.D.  
CHECKED BY: A.A.C.