

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	2222.3B	COOK	77	10
STA. 12+06.00		TO STA.16+17.11		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONCRETE CURB, TYPE B (FT)

BEGIN STA	END STA	LENGTH
12+39	12+53	LT 41.9 FT
13+02	13+53	LT 3.5 FT
15+43	15+92	LT 3.8 FT

BEGIN STA	END STA	LENGTH
12+34	12+53	RT 47.4 FT
13+01	13+53	RT 4.2 FT
15+41	15+92	RT 3.9 FT
51+63	51+79	RT 25.8 FT

TOTAL = 131 FT

COMBINATION CONCRETE CURB AND GUTTER, TYPE B6.12 (FT)

BEGIN STA	END STA	LENGTH
12+07	12+61	131.7 FT
51+65	51+73	8.8 FT

TOTAL = 141 FT

COMBINATION CONCRETE CURB AND GUTTER, TYPE B6.12 (SPECIAL) (FT)

BEGIN STA	END STA	LENGTH
12+94	13+54	148.4 FT
15+41	16+01	135.5 FT

TOTAL = 282 FT

COMBINATION CONCRETE CURB AND GUTTER REMOVAL (FT)

BEGIN STA	END STA	LENGTH
12+07	12+61	131.70 FT
12+94	13+54	146.40 FT
15+41	16+01	135.50 FT
51+65	51+73	8.80 FT

TOTAL = 422 FT

MEDIAN REMOVAL (SQ FT)

BEGIN STA	END STA	AREA
12+17.12	12+33.54	43 SQ FT
15+61.54	15+77.96	42 SQ FT

TOTAL = 85 FT

CHAIN LINK FENCE, 4' (FT)

STATION	OFFSET	TO	OFFSET	LENGTH
13+03.00	35.5'	RT	45.5'	10.00 FT
13+03.00	36.0'	LT	46.0'	10.00 FT
15+92.50	35.5'	RT	45.5'	10.00 FT
15+92.50	35.5'	RT	45.5'	10.00 FT

TOTAL = 40 FT

CHAIN LINK FENCE REMOVAL (FT)

STATION	OFFSET	TO	OFFSET	LENGTH
13+03.00	35.5'	RT	45.5'	10.00 FT
13+03.00	36.0'	LT	46.0'	10.00 FT
15+92.50	35.5'	RT	45.5'	10.00 FT
15+92.50	35.5'	RT	45.5'	10.00 FT

TOTAL = 40 FT

COLD MILLING EXISTING MEDIAN (SQ FT)

BEGIN STA	END STA	WIDTH	AREA	NOTES
12+06	12+48	3.5 FT	16.3 SQ FT	PRESTAGE MILLING
12+06	12+48	3.5 FT	16.3 SQ FT	MOT STAGE II MILLING

TOTAL = 33 FT

DOWNSPOUT CONNECTION (EACH)

STATION	OFFSET
13+59	25' LT
15+36	25' LT

TOTAL = 2 EACH

TEMPORARY CONCRETE BARRIER (FT)

BEGIN STA	END STA	LENGTH
GENOA AVENUE		250 FT
NB I-57 SHOULDER		375 FT
SB I-57 SHOULDER		350 FT

TOTAL = 975 FT

TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS (SQ FT)

STATION	OFFSET	SQ FT	NOTES
15+35	10.0 LT	21.1	"ONLY" - MOT STAGE 1
15+60	10.0 LT	15.2	LT ARROW - MOT STAGE 1

TOTAL = 36 SQ FT

TEMPORARY PAVEMENT MARKING - LINE 4" (FT)

BEGIN STA	END STA	LENGTH	NOTES
13+14.88	15+71.90	514 FT	DOUBLE YELLOW - MOT STAGE 1

TOTAL = 514 FT

TEMPORARY PAVEMENT MARKING - LINE 6" (FT)

BEGIN STA	END STA	LENGTH	NOTES
640+23.92	644+09.95	375 FT	I-57 NB MOT Stage 2 (bottom edge of Temp Conc Barr)
642+26.32	645+64.68	350 FT	I-57 SB MOT Stage 2 (bottom edge of Temp Conc Barr)

TOTAL = 725 FT

WET REFLECTIVE TEMPORARY TAPE, TYPE III - LETTERS AND SYMBOLS (SQ FT)

STATION	OFFSET	SQ FT	NOTES
15+35	21.5 RT	21.1	"ONLY" - MOT STAGE 2
15+60	21.5 RT	15.2	LT ARROW - MOT STAGE 2

PRIOR TO PERMANENT MARKINGS

STATION	OFFSET	SQ FT	NOTES
13+32	6.5 RT	22.9	ONLY
13+32	17.4 RT	22.9	ONLY
13+34	7.9 LT	15.8	LT ARROW
13+34	17.7 LT	11.2	STR ARROW
13+55	18.0 RT	15.8	LT ARROW
13+55	6.6 RT	15.8	LT ARROW
13+58	6.3 LT	22.9	ONLY
13+59	17.7 LT	22.9	ONLY
15+08	6.5 RT	22.9	ONLY
15+08	17.4 RT	22.9	ONLY
15+10	7.9 LT	15.8	LT ARROW
15+10	17.7 LT	11.2	STR ARROW
15+33	18.0 RT	15.8	LT ARROW
15+33	6.6 RT	15.8	LT ARROW
15+33	6.3 LT	22.9	ONLY
15+34	17.7 LT	22.9	ONLY

TOTAL = 337 SQ FT

PLOT DATE = Thursday, March 04, 2010
 FILE NAME = S:\11-CADD\101-10-09-11-0500\cadd\p1.dgn
 PLOT SCALE = 5001
 USER NAME = 3619



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULES OF QUANTITIES
SHEET 2 OF 3
GENOA AVENUE OVER FAI-57

SCALE: VERT. NONE
 HORIZ. DATE: 3/1/2010
 DRAWN BY: E.D.
 CHECKED BY: A.A.C.