



**NOTES**

Cost of Anchor Bolt and Plate included with Concrete Superstructure.

\* For Pay Items. See Electrical Plans

\*\* Epoxy grout d<sub>11</sub>(E) bars in 9" (Min). Drill holes according to Section 584 of the Standard Specifications.

\*\*\* 4-#6 d<sub>11</sub>(E) bars at 12" cts. EF Typical between existing sets of rebar unless noted otherwise.

Cost of Anchor Bolt Assembly included with Concrete Superstructure

<p>LIN ENGINEERING, LTD. Consulting Engineers Chatham, Illinois</p>	SHEET NO. 28	F.A.I. RTE. 57	SECTION 2222.3B	COUNTY COOK	TOTAL SHEETS 77	SHEET NO. 58
	32 SHEETS	CONTRACT NO. 62119		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		