



# OPTION 1




## OPTION 2

### TYPICAL TEMPORARY RAMP



TYPICAL BUTT JOINT AND HMA TAPER FOR MILLING AND RESURFACING

PROP. HMA OR PCC SURFACE REMOVAL - BUTT JOINT SAW CUT (INCLUDED IN THE COST OF HMA OR P.C.C. SURFACE REMOVAL EXIST. HMA OR PCC SURFACE 30'-0" (9.0 m) (NOTE "A") 15'-0" (4.5 m) (NOTE "B") - BUTT JOINT) (NOTE "D") 13/4 (45) FOR E AND F MIX 11/2 (40) FOR C AND D MIX \* \* EXIST. PAVEMENT BUTT JOINT DETAIL



# TYPICAL BUTT JOINT AND HMA TAPER FOR RESURFACING ONLY

\* \* PC CONCRETE, HMA OR HMA RESURFACED PAVEMENT.

#### NOTES

- A: MAINLINE ROADWAYS AND MAJOR SIDE ROADS.
- B: MINOR SIDE ROADS.
- C: THE TEMP. RAMP SHALL BE CONSTRUCTED IMMEDIATELY UPON REMOVAL OF THE EXISTING HMA SURFACE.
- D: THE BUTT JOINT SHALL BE CONSTRUCTED IMMEDIATELY PRIOR TO PLACING THE PROPOSED HMA COURSES.
- E: TAPER THE TEMP. RAMP AT A RATE OF 3'-O" (900 mm) PER 1 INCH (25 mm) OF MILLING THICKNESS.
- F: INSTALLATION AND REMOVAL OF THE 4'-6" (1.35 m) TEMP. RAMP IS INCLUDED IN COST OF HMA SURFACE REMOVAL - BUTT JOINT
- G: SEE ARTICLE 406.08 AND 406.14 OF THE STANDARD SPECIFICATIONS FOR "HMA AND/OR PCC SURFACE REMOVAL, BUTT JOINT".
- \* SEE TYPICAL SECTIONS FOR MILLING THICKNESS.

\*\* \* 20'-0" (6.1 m) PER 1 (25) RESURFACING (NOTE "A") 10'-0" (3.0 m) PER 1 (25) RESURFACING (NOTE "B")

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS

REVISIONS

#### BASIS OF PAYMENT:

THE BUTT JOINT WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER SOUARE YARD (SOUARE METER)
FOR "HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT" OR FOR "PORTLAND CEMENT CONCRETE SURFACE REMOVAL- BUTT JOINT".

| NAME       | DATE     |   |
|------------|----------|---|
| M. DE YONG | 6-13-90  |   |
| M. DE YONG | 7-3-90   |   |
| M. DE YONG | 3-27-92  |   |
| R. SHAH    | 09/09/94 |   |
| R. SHAH    | 10/25/94 |   |
| A. ABBAS   | 03/21/97 |   |
| M. GOMEZ   | 04/06/01 |   |
| R. BORO    | 01/01/07 | S |
|            |          | 2 |
|            |          |   |

ILLINOIS DEPARTMENT OF TRANSPORTATION

BUTT JOINT AND HMA TAPER DETAILS

SCALE: VERT. NONE

DRAWN BY CHECKED BY

BD400-05 (VI=BD32)

CONTRACT NO. 62119
COUNTY TOTAL SHEET NO.

77 66

COUNTY

COOK

TO STA. 16+17.11

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT

SECTION

57 2222.3B STA. 12+06.00