

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

URBAN

CODE NUMBER	PAY ITEM	UNIT	100% STATE TOTAL QUANTITY Y009
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	385
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	295
20101000	TEMPORARY FENCE	FOOT	843
20101100	TREE TRUNK PROTECTION	EACH	19
20200100	EARTH EXCAVATION	CU YD	704
20400800	FURNISHED EXCAVATION	CU YD	1,412
20800150	TRENCH BACKFILL	CU YD	81
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	1,799
25002014	SEEDING, CLASS 4A (MODIFIED)	ACRE	0.5
25100900	TURF REINFORCEMENT MAT	SQ YD	1,799
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	149
28000400	PERIMETER EROSION BARRIER	FOOT	707
28000500	INLET AND PIPE PROTECTION	EACH	3
28100207	STONE RIPRAP, CLASS A4	TON	1,572
28200200	FILTER FABRIC	SQ YD	710
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	163
50104400	CONCRETE HEADWALL REMOVAL	EACH	1
50104600	CONCRETE RETAINING WALL REMOVAL	FOOT	11
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	124

• SPECIALTY ITEM

SUMMARY OF QUANTITIES

URBAN

CODE NUMBER	PAY ITEM	UNIT	100% STATE TOTAL QUANTITY Y009
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	88
55100900	STORM SEWER REMOVAL 18"	FOOT	54
55101200	STORM SEWER REMOVAL 24"	FOOT	42
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5
60242801	INLETS, SPECIAL, NO. 5	EACH	3
60255410	CATCH BASINS TO BE CLEANED	EACH	5
60500050	REMOVING CATCH BASINS	EACH	3
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	163
66700095	PERMANENT SURVEY MARKERS	EACH	2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2
A2005814	TREE, PLATANUS OCCIDENTALIS (SYCAMORE), 3/4" CALIPER, BALLED AND BURLAPPED	EACH	2
A2006414	TREE, QUERCUS ALBA (WHITE OAK), 3/4" CALIPER, BALLED AND BURLAPPED	EACH	15
A2006714	TREE, QUERCUS MACROCARPA (BUR OAK), 3/4" CALIPER, BALLED AND BURLAPPED	EACH	8
A2007114	TREE, QUERCUS RUBRA (RED OAK), 3/4" CALIPER, BALLED AND BURLAPPED	EACH	15
A2007814	TREE, TILIA AMERICANA (AMERICAN LINDEN/ BASSWOOD), 3/4" CALIPER, BALLED AND BURLAPPED	EACH	4
Z0013798	CONSTRUCTION LAYOUT	L SUM	1

• SPECIALTY ITEM