

SCHEDULE OF QUANTITIES

63000003	STEEL PLATE BEAM GUARD RAIL, TYPE A, 9 FOOT POSTS FOOT	LOCATION MAINLINE				REMARKS
	300.0	RT	649 + 50	TO	652 + 50	
TOTAL	300.0					
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT EACH	LOCATION MAINLINE				REMARKS
	1.0	LT	651 + 37	TO	651 + 88	
	1.0	LT	654 + 00	TO	654 + 50	
	1.0	RT	649 + 00	TO	649 + 50	
	1.0	RT	652 + 50	TO	653 + 00	
TOTAL	4.0					
63200310	GUARDRAIL REMOVAL FOOT	LOCATION MAINLINE				REMARKS
	100.0	RT	650 + 83	TO	651 + 83	
	100.0	LT	651 + 40	TO	652 + 40	
TOTAL	200.0					
63500105	DELINEATORS EACH	LOCATION MAINLINE				REMARKS
	1.0	RT	649 + 00			
	1.0	RT	651 + 25			
	1.0	LT	651 + 50			
	1.0	LT	652 + 05			
	1.0	RT	653 + 00			
	1.0	LT	654 + 38			
TOTAL	6.0					
66700305	PERMANENT SURVEY MARKERS, TYPE II EACH	LOCATION MAINLINE				REMARKS
	2.0		647 + 00	TO	657 + 00	
TOTAL	2.0					
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS EACH	LOCATION MAINLINE				REMARKS
	1.0		648 + 28	TO	665 + 00	
TOTAL	1.0					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4" FOOT	LOCATION				REMARKS
	675.0		647 + 90	TO	654 + 60	INSIDE EDGE WHITE STAGE II
	416.0		649 + 44	TO	653 + 60	OUTSIDE EDGE WHITE STAGE II
	722.0		648 + 20	TO	655 + 40	INSIDE EDGE WHITE STAGE III
	600.0		647 + 22	TO	653 + 72	OUTSIDE EDGE WHITE STAGE III
TOTAL	2,413.0					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24" FOOT	LOCATION				REMARKS
	13.0	LT	650 + 50			STAGING STOP BAR
	13.0	RT	652 + 50			STAGING STOP BAR
TOTAL	26.0					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL SQ_FT	LOCATION				REMARKS
	26.0	LT	650 + 50			STAGING STOP BAR
	26.0	RT	652 + 50			STAGING STOP BAR
	224.8		647 + 90	TO	654 + 60	INSIDE EDGE WHITE STAGE II
	138.5		649 + 44	TO	653 + 60	OUTSIDE EDGE WHITE STAGE II
	240.4		648 + 20	TO	655 + 40	INSIDE EDGE WHITE STAGE III
	199.8		647 + 22	TO	653 + 72	OUTSIDE EDGE WHITE STAGE III
TOTAL	855.5					

70400100	TEMPORARY CONCRETE BARRIER FOOT	LOCATION				REMARKS
	462.5		649 + 23	TO	653 + 85	STAGING
TOTAL	462.5					
70400200	RELOCATE TEMPORARY CONCRETE BARRIER FOOT	LOCATION				REMARKS
	462.5		649 + 23	TO	653 + 85	STAGING
TOTAL	462.5					
78001110	PAINT PAVEMENT MARKING - LINE 4" FOOT	LOCATION				REMARKS
	387.5		647 + 75	TO	655 + 50	CENTERLINE YELLOW PASSING (2 APPLICATIONS)
	1550.0	LT	647 + 75	TO	655 + 50	SHOULDER WHITE (2 APPLICATIONS)
	1550.0	RT	647 + 75	TO	655 + 50	SHOULDER WHITE (2 APPLICATIONS)
TOTAL	3,487.5					
78200410	GUARDRAIL MARKERS, TYPE A EACH	LOCATION MAINLINE				REMARKS
	5.0	LT	651 + 87	TO	654 + 00	
	8.0	RT	649 + 50	TO	652 + 50	
TOTAL	13.0					
78201000	TERMINAL MARKER - DIRECT APPLIED EACH	LOCATION MAINLINE				REMARKS
	1.0	LT	651 + 37			
	1.0	LT	654 + 50			
	1.0	RT	649 + 00			
	1.0	RT	653 + 00			
TOTAL	4.0					
78300100	PAVEMENT MARKING REMOVAL SQ_FT	LOCATION				REMARKS
	27.5		647 + 75	TO	651 + 05	CENTERLINE YELLOW PASSING
	258.1	LT	647 + 75	TO	655 + 50	SHOULDER WHITE
	258.1	RT	647 + 75	TO	655 + 50	SHOULDER WHITE
TOTAL	543.6					
X4060310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50, SPECIAL TON	LOCATION				REMARKS
	98.0	RT	649 + 00	TO	654 + 50	WIDENING
	83.8	LT	649 + 00	TO	654 + 50	WIDENING
	34.3	RT	651 + 05	TO	652 + 10	TEMP PATCH
	11.1	LT	651 + 25	TO	652 + 10	WIDENING TO BE REMOVED AND REPLACED IN STAGING
TOTAL	227.2					
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 EACH	LOCATION MAINLINE				REMARKS
	1.0		649 + 30			STAGE II
	1.0		653 + 60			STAGE II
TOTAL	2.0					
Z0030350	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 EACH	LOCATION MAINLINE				REMARKS
	1.0		649 + 05			STAGE III
	1.0		653 + 85			STAGE III
TOTAL	2.0					