

SUMMARY OF QUANTITIES					90% FED 10% STATE CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QTY	RDWY 1000	046-	046-	046-	046-	046-	
					0018 X071-2A	0019 X071-2A	0083 X271-2A	0084 X271-2A	0085 X271-2A	
20200100	EARTH EXCAVATION	CU YD	312	312						
20300100	CHANNEL EXCAVATION	CU YD	2182		1091	1091				
20400800	FURNISHED EXCAVATION	CU YD	2905	2905						
21400100	GRADING AND SHAPING DITCHES	FOOT	250	250						
* 25000210	SEEDING, CLASS 2A	ACRE	12.8	12.8						
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1151	1151						
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1151	1151						
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1151	1151						
* 25100115	MULCH, METHOD 2	ACRE	7.7	7.7						
* 25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	26796	26796						
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2558	2558						
28000305	TEMPORARY DITCH CHECKS	FOOT	420	420						
28000500	INLET AND PIPE PROTECTION	EACH	11	11						
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	240	240						
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	71842	71842						
40600300	AGGREGATE (PRIME COAT)	TON	798	798						
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	120	120						
40600545	LEVELING BINDER (HAND METHOD), N90	TON	401	401						
40600895	CONSTRUCTING TEST STRIP	EACH	4	4						
40600990	TEMPORARY RAMP	SQ YD	172	172						
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	12263	12263						
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	37802	37802						
40603520	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	8325	8325						
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	24636	24636						
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	400	400						
44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SQ YD	397341	397341						
44000186	HOT-MIX ASPHALT SURFACE REMOVAL, 9"	SQ YD	1780	1780						
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	802		401	401				
44200620	CLASS A PATCHES, TYPE II, 14 INCH	SQ YD	114	114						
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	128	128						
44213000	PATCHING REINFORCEMENT	SQ YD	114	114						
44213200	SAW CUTS	FOOT	1532	1532						

FILE NAME =	USER NAME = braboypc	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\braboypc\dms30564\dets11s.dgn	DRAWN -	REVISED -	57			(46-1.2)BS-3 & I	KANKAKEE	115	3	
PLOT SCALE = 1250.0000' / IN.	CHECKED -	REVISED -	CONTRACT NO. 66608							
PLOT DATE = Mar 25, 2010 - 01:01:20 PM	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							
					SCALE: _____	SHEET NO. ___ OF ___ SHEETS		STA. _____ TO STA. _____		