

SUMMARY OF QUANTITIES					90% FEDERAL 10% STATE					
CODE NO	ITEM	UNIT	TOTAL QTY	CONSTRUCTION TYPE CODE						
				RDWY	046-	046-	046-	046-	046-	
				I000	X071-2A	X071-2A	X083-2A	X084-2A	X085-2A	
67100100	MOBILIZATION	L SUM	1	1						
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4	4						
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	1						
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1				0.33	0.33	0.34	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	90	90						
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12						
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	20907	20907						
* 70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	193936	193936						
* 70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	22350	22350						
* 70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	2840	2840						
* 70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	700	700						
* 70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	100	100						
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	8816	8816						
* 70400100	TEMPORARY CONCRETE BARRIER	FOOT	780	780						
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	660	660						
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	193936	193936						
* 78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	2840	2840						
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	700	700						
* 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	100	100						
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2320	2320						
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	8	8						
* 78200405	GUARDRAIL MARKERS	EACH	110	110						
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	20	20						
* 78202000	TERMINAL MARKER - POST MOUNTED	EACH	1	1						
78300100	PAVEMENT MARKING REMOVAL	SQ FT	31549	31549						
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2354	2354						
X0300247	REMOVE WOOD POST	EACH	170	170						
X0321468	PLUG EXISTING DECK DRAINS	EACH	16				8	8		
X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	802		401	401				
X0322729	MATERIAL TRANSFER DEVICE	TON	83591	83591						
X0323818	CLEANING AND PAINTING EXPOSED REBAR	SQ FT	80				25	45	10	

FILE NAME =  
c:\pw\_work\p1dot\braboygo\dms30564\dets11a.dgn

USER NAME = braboygo  
PLOT SCALE = 1250.0000' / IN.  
PLOT DATE = Mar 25, 2010 - 01:02:57 PM

DESIGNED - ---  
DRAWN - ---  
CHECKED - ---  
DATE - ---

REVISED - ---  
REVISED - ---  
REVISED - ---  
REVISED - ---

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: \_\_\_\_\_ SHEET NO. \_\_\_ OF \_\_\_ SHEETS STA. \_\_\_\_\_ TO STA. \_\_\_\_\_

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
51	146-1.218S-3-&-1	KANKAKEE	115	5
CONTRACT NO. 66608			ILLINOIS FED. AID PROJECT	