

GUARDRAIL										
	DL PL	TERM MKR DIR APP	TBT TY I SP TANG	SPBGR TY A 6' POSTS	TBT TY 6	TBT TY 6 A	TBT TY 2	GR MKR	HMA SHLDS 6" FOR SPBGR STABILIZATION	GR REMOVAL
STA TO STA		EA	EA	FT	EA	EA	EA	EA	SQ YD	FOOT
NORTHBOUND										
STA 417+53 TO STA 420+78 (ST GEORGE RD E5000N) SN 046-0081 (E6000N RD) SN 046-0086	DL	1	1	235	1			4	113	261
STA 525+04 TO STA 528+29 (E 7000N RD) SN 046-0085	DL	1	1	235	1			4	113	267
STA 545+05 TO STA 549+20 (SN 046-0019) (1)	PL	1	1	325		2	1	6	143	373
STA 545+16 TO STA 549+21 (SN 046-0019) (1)	DL	1	1	235		2	1	4	113	272
STA 637+89 TO STA 641+14 (MANTENO RD) SN 046-0058	DL	1	1	235	1			5	113	380
STA 694+96 TO STA 698+21 (E 10000N RD) SN 046-0084	DL	1	1	235	1			4	113	268
STA 812+05 TO STA 815+30 (E 12000N RD) SN 046-0083	DL	1	1	235	1			4	113	230
(NB) SUBTOTAL		8	8	1970	6	4	2	36	934	2431

1. THE DEPARTING ENDS OF SN 046-0018 AND 046-0019 IN BOTH THE PL AND DL SHALL END WITH A TYPE 6A AND TYPE 2 END SECTIONS-
ATTACH THE TYPE 6A TO THE STEEL RAILING, TYPE 2399

GUARDRAIL (CONT.)										
	DL PL	TERM MKR DIR APP	TBT TY I SP TANG	SPBGR TY A 6' POSTS	TBT TY 6	TBT TY 6 A	TBT TY 2	GR MKR	HMA SHLDS 6" FOR SPBGR STABILIZATION	GR REMOVAL
STA TO STA		EA	EA	FT	EA	EA	EA	EA	SQ YD	FOOT
SOUTHBOUND										
STA 420+95 TO STA 424+20 (ST GEORGE RD E5000N) SN 046-0081 (E6000N RD) SN 046-0086	DL	1	1	235	1			5	113	351
STA 528+18 TO STA 531+43 (E 7000N RD) SN 046-0085	DL	1	1	235	1			4	113	267
STA 550+02 TO STA 554+17 (SN 046-0018)*	PL	1	1	325		2	1	6	143	377
STA 549+88 TO STA 554+03 (SN 046-0018)*	DL	1	1	235		2	1	4	113	275
STA 641+33 TO STA 644+58 (MANTENO RD) SN 046-0058	DL	1	1	235	1			5	113	380
STA 697+81 TO STA 701+06 (E 10000N RD) SN 046-0084	DL	1	1	235	1			4	113	268
STA 814+95 TO STA 818+20 (E 12000N RD) SN 046-0083	DL	1	1	235	1			4	113	226
(SB) SUB TOTAL		8	8	1970	6	4	2	37	934	2524
RAMPS										
RAMP A		1	1	975			1	12	360	1038
RAMP B		2	2	1084				16	410	1184
RAMP D		1	1	652			1	9	250	715
(SB & NB) GRAND TOTAL		20	20	6651	12	8	6	110	2888	7892

1. THE DEPARTING ENDS OF SN 046-0018 AND 046-0019 IN BOTH THE PL AND DL SHALL END WITH A TYPE 6A AND TYPE 2 END SECTIONS. ATTACH THE TYPE 6A TO THE STEEL RAILING, TYPE 2399

FILE NAME =	USER NAME = braboyco	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES			F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\braboyco\dms30954\dms30954.dgn	DRAWN -	REVISED -	57					(46-1.2)RS-3-&.I	KANKAKEE	115	11	
PLOT SCALE = 1/2" = 1271.9487' / IN.	CHECKED -	REVISED -	CONTRACT NO. 66608									
PLOT DATE = Mar 25, 2010 - 12:33:58 PM	DATE -	REVISED -	SCALE: _____		SHEET NO. _____ OF _____ SHEETS	STA. _____ TO STA. _____	ILLINOIS FED. AID PROJECT					