

STAGE CONSTRUCTION ITEMS

LOCATION	STA	LENGTH	TEMPORARY CONCRETE BARRIER FOOT	RELOCATE TEMP CONC BARRIER FOOT	IMPACT ATTENUATORS NRD,TL3 EACH	RELOCATE IMPACT ATTENUATORS NRD,TL3 EACH	HMA(1) BASE CSE 9" SQ YD	HMA SURF REMOVAL, 9" SQ YD	WORK ZONE PVT MK REMOVAL(2) SQ FT	PAVEMENT MARKING REMOVAL(3) SQ FT	WET TEMP PVT MK TAPE, TYPE III-4"		
											WHITE FOOT	YELLOW FOOT	
STAGE I													
NBL	530+94 TO 553+64	2270							757	125.0		2270.0	
	545+94 TO 553+64	770							257	257.0	770.0		
SBL	545+60 TO 553+30	770							257	257.0		770.0	
	545+60 TO 568+30	2270							757	125.0	2270.0		
STAGE II													
NBL	532+64 TO 551+94	1930							643	125.0		1930.0	
	547+64 TO 551+94	430							144	144.0	430.0		
SBL	547+30 TO 566+60	1930							643	125.0	1930.0		
	547+30 TO 551+60	430							144	144.0		430.0	
STAGE I													
NBL	546+64 TO 550+54	390	390.0		1								
SBL	548+70 TO 552+60	390	390.0		1								
STAGE II													
NBL	547+24 TO 550+54	330		330		1							
SBL	548+70 TO 552+00	330		330		1							
NBL ON 10' SHLD (FOR STAGE I TRAFFIC)*													
	545+94 TO 553+64	670					745	745					
SBL ON 10' SHLD (FOR STAGE I TRAFFIC)*													
	545+60 TO 553+30	670					745	745					
NBL ON 4' SHLD (FOR STAGE II TRAFFIC)**													
	547+64 TO 551+94	330					145	145					
SBL ON 4' SHLD (FOR STAGE II TRAFFIC)**													
	285+75 TO 293+60	330					145	145					
STA 364+25 TO STA 818+00 NBL & SBL (4)													
TOTALS													
			780.0	660.0	2.0	2.0	1780.0	1780.0	2588.0	31549.0	30247.0	5400.0	5400.0
												11240.0	

*DEDUCT 100' FOR BRIDGE
 (1) TO BE PERFORMED PRIOR TO STAGE I CONSTRUCTION-EXISTING SHOULDER IS 9". LAST 1 1/2" LIFT OF 9" THICKNESS SHALL BE AS SPECIFIED IN MIX TABLE SINCE THIS WILL BE FINAL WEARING SURFACE
 (2) WK ZONE PVT MK REMOVAL IS TO REMOVE THE WET TEMP PVT MK TAPE
 (3) PAVEMENT MARKING REMOVAL IS TO REMOVE EXISTING PAVEMENT MARKINGS PRIOR TO STAGE I CONSTRUCTION
 (4) PRIOR TO STAGE I CONSTRUCTION, ALONG THE DL EDGE LINE

PIPE UNDERDRAIN OUTLET EXTENSION (SPECIAL)	
LOCATION**	PIPE UNDERDRAIN OUTLET EXT. (SPECIAL) EACH
NORTHBOUND LANE	
STA 674+50 TO 815+00	15
TOTALS	15

** QUANTITY IS ESTIMATED BASED ON CROSS SECTIONS AND CURRENT UNDERDRAIN SPACING

FILE NAME =	USER NAME = braboygo	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\pwi\dot\braboygo\dms30564\deta11s.dgn	DRAWN -	REVISED -	57			(46-1.2)BS-3 & I	KANKAKEE	115	14	
PLOT SCALE = 1271.9487' / IN.	CHECKED -	REVISED -	SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____			CONTRACT NO. 66608				
PLOT DATE = Mar 25, 2010 - 12:33:24 PM	DATE -	REVISED -				ILLINOIS FED. AID PROJECT				