

PAVEMENT MARKING SCHEDULE						
STATION TO STATION		LENGTH	SHORT-TERM CENTERLINE	WORKZONE PAVT MKG REMOVAL	RAISED REFLECTIVE PAVT MKR	RAISED REFLECTIVE PAVT MKR REMOVAL
		(FT)	(FT)	(SQ FT)	(EACH)	(EACH)
US 54						
+20	1+90	170	34	6	5	5
+28	+45	17	3	1	5	5
IL 106						
7+80	9+00	120	24	4	5	5
STA EQN 1000+90.00BK = 7+56.90AH						
1000+30	1137+00	13,670	2734	456	171	171
STA.EQN 1137+00.00BK = 131+55.25AH						
131+55	175+00	4,345	869	145	54	54
		SUB-TOTAL	3664	611	240	240
		TOTALS	3664	611	240	240

PAINT PAVT MKG 5"						
STATION TO STATION		LENGTH	EDGE OF PAVEMENT	DBL NO PASS	SINGLE NO PASS	SKIP DASH
		(FT)	(FT)	(FT)	(FT)	(FT)
US 54						
+20	1+90	170	340	--	--	--
+28	+45	17	34	--	--	--
IL 106						
7+80	9+00	120	240	--	--	--
STA EQN 1000+90.00BK = 7+56.90AH						
1000+30	1033+30	3,300	6,600	--	--	825
1033+30	1137+00	10,370	20,740	1880	4280	2123
STA.EQN 1137+00.00BK = 131+55.25AH						
131+55	175+00	4,345	8,690	--	3470	868
		SUB-TOTALS	36644	1880	7750	3815
		TOTAL	50089			

STATION TO STATION	PREFORMED PLASTIC TYPE B - INLAID		THERMOPLASTIC		PREFORMED LETTERS & SYMBOLS
	6" WHITE	24" WHITE	5" YELLOW	12" YELLOW	
	(FT)	(FT)	(FT)	(FT)	(SQ FT)
US 54 / IL 106 INTERSECTION					
CROSS WALKS	444	--		--	--
STOP BARS	--	110		--	--
TURN LANE LINE	280	--	1356	--	--
CHANNELIZATION	--	--	390	70	--
TURN ARROWS	--	--		--	130
TOTALS	724	110	1746	70	130

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
e:\pwwork\pwidot\LAUGHLINRL\dna25724\672b45-sh-t-schedule.dgn		DRAWN -	REVISED -
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = Apr-08-2010 09:01:28AM		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO. 2 OF 3 SHEETS	STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
757	(20X)RS-5; (21X)RS-3	PIKE	34	5
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 72B45	