## **STATE OF ILLINOIS**

## **DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS**

FOR INDEX OF SHEETS, SEE SHEET NO. 2


## **IDOT HIGHWAY STANDARDS**

00000105	63000108	63030105
631011-06	635006-03	63501102
701101-02	701106-02	701901-01

# **PROPOSED** HIGHWAY PLANS

F.A.P. ROUTE 662 (IL 4) SECTION 3 I-10 PROJECT HSIP-0662 (064) PIER PROTECTION **SANGAMON COUNTY** 

C-96-179-10



GROSS LENGTH = 369.40 FT. = 0.070 MILE NET LENGTH = 369.40 FT. = 0.070 MILE ADT = 30700 (2007)

SANGAMON ILLINOIS CONTRACT NO. 72048

#### D-96-179-10



STATE OF ILLINOIS

Christine M. Reed &

PRINTED BY THE AUTHORITY OF THE STATE OF ILLINOIS

ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES, IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

 $\circ$ 

PROJECT ENGINEER: JOHN NEGANGARD (217) 782-6990 PROJECT MANAGER: MARK DUST (217) 785-0597

CONTRACT NO. 72D48

INDE	X OF SHEETS							
SHEET NO.	DISCRIPTION							
1	COVER SHEET							
2	GENERAL NOTES							
3	SUMMARY OF QUANTITIES							
3	SCHEDULE OF QUANTITIES							
4	PLAN SHEET							
5	HOLE PLACEMENT DETAILS							

### GENERAL NOTES

- 1. ANY REFERENCE TO THE STANDARDS THROUGH OUT THE PLANS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT AS INCLUDED IN THE PLANS.
- 2. EXISTING TRAFFIC SIGNAL FIBER OPTIC CABLE IS PRESENT WITHIN THE LIMITS OF THIS PROJECT. THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING J.U.L.I.E. A MINIMUM OF 48 HOURS PRIOR TO COMMENCING WORK TO HAVE THIS CABLE LOCATED. 1-800-892-0123
- 3. THE CONTRACTOR WILL BE REQUIRED TO CONTACT THE OPERATIONS ENGINEER (217) 782-7314 AT LEAST 72 HOURS PRIOR TO DRIVING ANY POSTS.
- 4. THE CONTRACTOR WILL BE REQUIRED TO REPAIR ANY AREAS OF TURF THAT ARE DAMAGED DURING THE EXECUTION OF THIS CONTRACT.
- 5. ALL GUARDRAIL SHALL HAVE A PRELIMINARY LAYOUT. GUARDRAIL POSTS SHALL BE ADJUSTED SO AS TO MISS ANY SHOULDER DRAINS, INLETS, PIPE CULVERTS, STORM SEWER, FIBER OPTIC INTERCONNECT CABLE OR ANY OTHER HAZARD THAT MAY INTERFERE WITH GUARDRAIL CONSTRUCTION.

DISTRICT SIX
EXAMINED 3/22 2010
OPERATIONS ENGINEER
EXAMINED Mach 17 20 10  PROGRAM DEVELOPMENT ENGINEER
EXAMINED MARCH 19 20 10
PROGRAM IMPLEMENTATION ENGINEER

FILE NAME =	USER NAME = starkegc	DESIGNED	REVISED	
c:\pw_work\pwidot\starkegc\d0182857\sht-	gennote.dgn	DRAWN	REVISED	STAT
	PLOT SCALE = 100.0000 '/ IN.	CHECKED	REVISED	DEPARTMENT
	PLOT DATE = Mar-24-2010 10:55:30AM	DATE	REVISED	

OF	GENERAL NOTES		F.A.P. RTE.	SECTION	COUNTY	TOTAL	SHEET NO.	
	662	3 1-10	SANGAMON	5	2			
				CONTRACT	NO. 7	72D48		
DF.	SHEETS	STA.	TO STA		TIL THOSE EED AT	D DDO IECT		

	ILLINOIS DEPARTMENT O	F TRANSPORTA	TION						
	SUMMARY OF QU	ANTITIES	URBAN						
************	LOCATION OF WORK		SFTY-3J	CONSTRUCTION CODE TYPE					
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	SAFETY FUNDS 90% FED 10% STATE		·			
63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	250	250		·			
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2					
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2					
67100100	MOBILIZATION	L SUM	1	. 1					
78200410	GUARDRAIL MARKER, TYPE A	EACH	8	8					
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2					
K1009110	VEGETATION CONTROL SYSTEM	SQ YD	176	176					

		*************				
				GUARDRAIL SCHED	ULE	
LOCATION			OFFSET	STEEL PLATE BEAM GUARD RAIL	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	TRAFFIC BARRIER TERMINAL, TYPE 2
STATION	TO	STATION	LT / RT	FOOT	EACH	EACH
443+05.55 - 443+55.55			RT 14'		1	
443+55.55	-	444+80.55	RT 14'	RT 14' 125		
444+80.55			RT 14'			1
444+87.45 - 444+99.95			LT 14.5'			1
444+99.95 - 446+24.95			LT 14.5'	125		
446+24.95					1	
				·		
			TOTAL =	250	2	2

	V	EGETATION CO	NTROL SCHED	ULE
LO	CATI	ON	OFFSET	VEGETATION CONTROL SYSTEM
STATION	TO	LT / RT	SQ YD	
443+00.00	-	444+98,00	RT 14'	88
444+82,00	-	446+80.00	LT 14.5'	88
			TOTAL =	176

FILE NAME =	USER NAME = laughlinrl	DESIGNED	REVISED -		SUMMARY OF QUANTITIES AND			F.A.P.	SECTION	COUNTY	TOTAL	SHEET			
c:\pw_work\PWIDOT\LAUGHLINRL\dØ182857\D	672D48-sht-schedule.dgn	DRAWN -	REVISED -	STATE OF ILLINOIS	SCHEDULE OF QUANTITIES					662	3 I-10	SANGAMON	5	3	
	PLOT SCALE = 100.0000 '/ IN.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION							CONTRAC	T NO. 7	2D48		
	PLOT DATE = Mar-24-2010 01:50:38PM	DATE -	REVISED -	****		SCALE: SHEET NO. OF SHEETS STA.		SCALE: SHEET NO. OF SHEETS STA. TO STA.		TO STA.		ILLINOIS FED.			

