GENERAL NOTES:

1. ANY REFERENCE TO THE STANDARDS THROUGHOUT THE PLANS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT AS INCLUDED IN THE PLANS.

2. NO EXCAVATION ANTICIPATED ON THIS PROJECT WHICH WOULD AFFECT UTILITIES. SHOULD ANY EXCAVATION BE REQUIRED, J.U.L.I.E. SHALL BE NOTIFIED A MINIMUM OF 48 HOURS IN ADVANCE - (800) 892-0123.

3. THE FOLLOWING APPLICATION RATES WERE USED FOR QUANTITY CALCULATIONS:

HMA SHOULDERS	0.056 T / SY*IN
PRIME COAT (BIT) - on Pavement	0.00038 T / SY

4. IN ADDITION TO FIELD SURVEYS AND AERIAL SURVEYS, PLAN DIMENSIONS AND DETAILS RELATIVE TO THE EXISTING FACILITIES HAVE BEEN TAKEN FROM EXISTING PLANS AND ARE SUBJECT TO CONSTRUCTION VARIATIONS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY SUCH DIMENSIONS AND DETAILS IN THE FIELD. SUCH VARIATIONS SHALL NOT BE A CAUSE FOR ADDITIONAL COMPENSATION DUE TO A CHANGE IN THE SCOPE OF THE WORK. HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE BID PRICE FOR THE WORK.

INDEX OF SHEETS:

1. COVER SHEET
2. GENERAL NOTES
3. SUMMARY OF QUANTITIES
4. SCHEDULE
5-6. TYPICAL CROSS SECTIONS

LIST OF STANDARDS:

642001-01
701101-02
701106-02
701400-04
701406-05
701411-06
701426-03
701901-01
780001-02
701301-03

THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE TO THIS PROJECT:

MIXTURE USES:	HMA SHOULDERS
LOCATION	I 72
AC/PG:	PG 64-22
DESIGN AIR VOIDS:	4 % @ N DESIGN = 50
MIXTURE COMPOSITION: (GRADATION MIXTURE)	IL 9.5 OR 12.5
FRICTION AGGREGATE:	MIX C

DISTRICT SIX

EXAMINED 3-9 20 10
Rie Walk
OPERATIONS ENGINEER

EXAMINED MARCH 19 20 10
Terry Fanelli
PROGRAM IMPLEMENTATION ENGINEER

EXAMINED March 9 20 10
QRM Li
PROGRAM DEVELOPMENT ENGINEER