Stage removal line

EXISTING DECK BEAM

1'-10'2"

Stage construction line-

1'-10/2"

See Detail I

or Detail II.

NEW SLAB

NOTES

Detail I - With Bar Splicer or Couplers:

Connect one (1) 1"x7"x10" steel P to the top layer of couplers with 2-5g" \$\phi\$ bolts screwed to coupler at approximate \$\mathbb{Q}\$ of each barrier panel.

Detail II - With Extended Reinforcement Bars:

Connect one (1) 1"x7"x 10" steel P to the concrete slab or concrete wearing surface with 2-5g" \$\phi\$

Expansion Anchors or cast in place inserts spaced between the top layer of reinforcement at approximate \$\mathbb{C}\$ of each barrier panel.

Cost of anchorage is included with Temporary Concrete Barrier.

The 1" x 7" x 10" plate shall not be removed until stage II construction forms and all reinforcement bars are in place and the concrete is ready to be placed.

SECTIONS THRU SLAB OR DECK BEAM

EXISTING SLAB

Stage removal line

Temporary Concrete Barrier
| See Standard 704001 |

Drill 3-14" \$\phi\$ Holes in existing

slab for 1" ϕ x 11" dowel bars.

Traffic side only. Cost included


with Temporary Concrete Barrier.


1'-10'2"

*** Dimension shown is minimum required embedment into concrete.

If hot-mix asphalt wearing surface is present, minimum embedment shall be in addition to wearing surface depth.

**** If existing deck beam is to remain in place after stage construction, embedment shall only be into wearing surface and not into existing deck beam concrete.





Top bars Detail I spacing

3" 3" Detail II

© 78" \$\phi\$ Holes

*© 1" x 1'2" Notch

STEEL RETAINER P 1" x 7" x 10"

* Required only with Detail II

** Wood blocks may be omitted when required to provide minimum stage traffic lane width. When the wood blocks are omitted, the concrete barrier shall be in direct contact with the steel retainer plate.

Johnson, Depp & Quisenberry
CONSULTING ENGINEERS
Springfield, Illinois

DESIGNED: JDQ DRAWN: SJS
CHECKED: DCD CHECKED: DCD

R-27 11-1-09

"W" = Top bars spacing + 4"

TEMPORARY CONCRETE BARRIER
FOR STAGE CONSTRUCTION
STRUCTURE NO. 058-0108(SB) & 0109(NB)

I	SHEET 3 OF 26	F.A.P. RTE.	SECTION				COUNTY	TOTAL SHEETS	SHEET NO.
1		322	(58-20)RS				MACON	151	105
I		STA. 235+00.78				CONTRACT	NO.	74150	
ł		FED. RO	AD DIST.	NO.	ILLINOIS	FED.	AID PROJECT		