



NOTE: EXISTING GAURDRAIL NOT SHOWN FOR CLARITY.

NOTE: CONTRACTOR SHALL PERFORM BRIDGE DECK SAW CUT ALONG STAGE I REMOVAL LINE PRIOR TO PLACING T.C.B. ON BRIDGE. ALONG THE ROADWAY, THE CONTRACTOR SHALL SAW CUT ALONG REMOVAL LINE PRIOR TO STAGE II. ALL WORK SHALL BE PERFORMED AT NIGHT WITH STANDARD 701421 FOR LANE CLOSURE. COST INCLUDED IN COST OF TRAFFIC CONTROL AND PROTECTION - STAGE I.

FILE NAME =	USER NAME = jheger	DESIGNED - MLS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TRAFFIC CONTROL PLAN - STAGE I	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
F:\880276\US 51 over I-72\4-CADD\4.2-TR	SHEETS\0774387-ah- staging-005.dgn	DRAWN - MLS	REVISED -			322	158-64HB-1B-1	MACON	149	25	
PLOT SCALE = 20.0000' / in.		CHECKED - SJK	REVISED -			US ROUTE 51		CONTRACT NO. 74387			
PLOT DATE = 3/15/2010		DATE -	REVISED -			SCALE: 1:20		SHEET NO. 5 OF 22 SHEETS		STA. 1155+00 TO STA. 1160+50	
						FED. ROAD DIST. NO. 7		ILLINOIS		FED. AID PROJECT	