
STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION Stage I traffic Stage I Removal Temp, Concrete Barrier See sheet 4 of 16. Roadway STAGE I REMOVAL Stage I Construction € Roadway STAGE I CONSTRUCTION Stage II Removal 14'-0'' Stage II Traffic - © Roadwav Temp. Concrete Barrier See sheet 4 of 16. STAGE II REMOVAL Stage II Construction STAGE II CONSTRUCTION DESIGNED J.E. KRAMER All sections are looking North. CHECKED P.E. COPPERNOLI Hatched area indicates Removal of Existing Structure. DRAWN AMBER SEIBER For quantity of Temporary Concrete Barrier, see Roadway Plans. CHECKED GRA

0790050-76126.dgn 03/02/2010 2:34:28 PM



TEMPORARY SHEET PILING AT ABUTMENTS

If the Contractor chooses to alter the temporary cantilevered sheet piling design requirements shown on the plans, a design submittal including plan details and calculations will be required for review and acceptance by the Engineer.

The Contractor shall connect the first sheet to the existing abutment wall to ensure stability of sheets driven to the top of the existing footing. This connection shall be reviewed and accepted by the Engineer and the cost included with Temporary Sheet Piling.

STAGE CONSTRUCTION DETAILS STRUCTURE NO. 079-0050

SHEET NO.3	F.A.P. RTE.	SECTION	COUNTY	TOTAL	SHEET NO.
	682	21BR, 21-I-1	RANDOLPH	77	42
21 SHEETS			CONTRACT	NO. 76	126
	FED. ROAD DIST. NO ILLINOIS FED. AID PROJECT				