

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	SN 031-0041(P) 401-2BR X071-2A	SN 031-0040(P) 1-2BR X071-2A	SN 031-0039(P) 1BR X071-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	12			12
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	46			46
20200100	EARTH EXCAVATION	CU YD	778	659	49	70
20300100	CHANNEL EXCAVATION	CU YD	3000	1770	290	940
20400800	FURNISHED EXCAVATION	CU YD	3854	961	1353	1540
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	398	130	130	138
25000200	SEEDING, CLASS 2	ACRE	1.75	0.75	0.5	0.5
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	175	75	50	50
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	175	75	50	50
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	175	75	50	50
25100115	MULCH, METHOD 2	ACRE	7.25	3.25	2	2
25100630	EROSION CONTROL BLANKET	SQ YD	988	988		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	635	335	150	150
28000400	PERIMETER EROSION BARRIER	FOOT	3909	1517	1042	1350
28000500	INLET AND PIPE PROTECTION	EACH	8	6	2	
28100105	STONE RIPRAP, CLASS A3	SQ YD	104	104		
28100106	STONE RIPRAP, CLASS A3 (SPECIAL)	SQ YD	201	92	40	69
28100109	STONE RIPRAP, CLASS A5	SQ YD	1948	766	521	661
28200200	FILTER FABRIC	SQ YD	2823	1532	561	730
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	31	31		
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	237	220	17	
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQ YD	704		371	333
40200700	AGGREGATE SURFACE COURSE, TYPE A 8"	SQ YD	462	392	70	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	411	411		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2.7	0.9	0.9	0.9
40600300	AGGREGATE (PRIME COAT)	TON	5.2	2.4	1.3	1.5
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	538	242	148	148
40600990	TEMPORARY RAMP	SQ YD	50		25	25
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	499.5	285.5	122	92
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	337.9	126.9	103	108
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	45	44	1	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	140	44	48	48
44000100	PAVEMENT REMOVAL	SQ YD	718	250	230	238

Rev.