

0310041-76410-04-TSEL.DGN AUG. 18, 2009

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BEAM #1

Location	Station	Offset from Ctrline	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Dead Load Deflection
Bk. N. Abut.	123+58.00	-12.92	453.29	453.29
⊕ Brg. N. Abut.	123+59.25	-12.92	453.29	453.29
A	123+69.25	-12.92	453.32	453.39
B	123+79.25	-12.92	453.35	453.47
C	123+89.25	-12.92	453.37	453.53
D	123+99.25	-12.92	453.38	453.55
E	124+09.25	-12.92	453.39	453.55
F	124+19.25	-12.92	453.39	453.52
G	124+29.25	-12.92	453.38	453.46
⊕ Brg. S. Abut.	124+40.75	-12.92	453.37	453.37
Bk. S. Abut.	124+42.00	-12.92	453.37	453.37

BEAM #2

Location	Station	Offset from Ctrline	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Dead Load Deflection
Bk. N. Abut.	123+58.00	-7.75	453.37	453.37
⊕ Brg. N. Abut.	123+59.25	-7.75	453.38	453.38
A	123+69.25	-7.75	453.41	453.47
B	123+79.25	-7.75	453.43	453.56
C	123+89.25	-7.75	453.45	453.61
D	123+99.25	-7.75	453.47	453.64
E	124+09.25	-7.75	453.47	453.64
F	124+19.25	-7.75	453.47	453.60
G	124+29.25	-7.75	453.47	453.54
⊕ Brg. S. Abut.	124+40.75	-7.75	453.45	453.45
Bk. S. Abut.	124+42.00	-7.75	453.45	453.45

BEAM #3

Location	Station	Offset from Ctrline	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Dead Load Deflection
Bk. N. Abut.	123+58.00	-2.58	453.45	453.45
⊕ Brg. N. Abut.	123+59.25	-2.58	453.46	453.46
A	123+69.25	-2.58	453.49	453.55
B	123+79.25	-2.58	453.51	453.64
C	123+89.25	-2.58	453.53	453.69
D	123+99.25	-2.58	453.55	453.72
E	124+09.25	-2.58	453.55	453.72
F	124+19.25	-2.58	453.55	453.68
G	124+29.25	-2.58	453.55	453.62
⊕ Brg. S. Abut.	124+40.75	-2.58	453.53	453.53
Bk. S. Abut.	124+42.00	-2.58	453.53	453.53

⊕ ROADWAY AND PROFILE GRADE

Location	Station	Offset from Ctrline	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Dead Load Deflection
Bk. N. Abut.	123+58.00	0.00	453.49	453.49
⊕ Brg. N. Abut.	123+59.25	0.00	453.50	453.50
A	123+69.25	0.00	453.53	453.60
B	123+79.25	0.00	453.55	453.68
C	123+89.25	0.00	453.57	453.73
D	123+99.25	0.00	453.59	453.76
E	124+09.25	0.00	453.59	453.76
F	124+19.25	0.00	453.59	453.72
G	124+29.25	0.00	453.59	453.66
⊕ Brg. S. Abut.	124+40.75	0.00	453.57	453.57
Bk. S. Abut.	124+42.00	0.00	453.57	453.57

Notes:
1. Elevations are at Top of Concrete.
2. See Sheet 3 of 21 for elevation locations.

TOP OF SLAB ELEVATIONS

DESIGNED	B.G.H.
CHECKED	L.D.G.
DRAWN	K.H.L.
CHECKED	B.G.H.

SHEET NO. 4	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	739	401-2BR	GREENE	150	37
21 SHEETS	S.N. 031-0041		CONTRACT NO. 76410		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT			

H.M. & G. NO. 6020.161