

0130039-74310-06-TSEL.DGN NOV. 30, 2009

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

**BEAM #1**

Location	Station	Offset from Ctrline	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Dead Load Deflection
Bk. S. Abut.	236+65.00	-15.00	444.56	444.56
⊕ Brg. S. Abut.	236+66.25	-15.00	444.56	444.56
A	236+76.25	-15.00	444.59	444.64
B	236+86.25	-15.00	444.60	444.69
C	236+96.25	-15.00	444.61	444.72
D	237+06.25	-15.00	444.61	444.72
E	237+16.25	-15.00	444.61	444.69
F	237+26.25	-15.00	444.59	444.63
⊕ Brg. N. Abut.	237+33.75	-15.00	444.58	444.58
Bk. N. Abut.	237+35.00	-15.00	444.58	444.58

**BEAM #2**

Location	Station	Offset from Ctrline	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Dead Load Deflection
Bk. S. Abut.	236+65.00	-9.00	444.67	444.67
⊕ Brg. S. Abut.	236+66.25	-9.00	444.67	444.67
A	236+76.25	-9.00	444.70	444.75
B	236+86.25	-9.00	444.71	444.80
C	236+96.25	-9.00	444.72	444.83
D	237+06.25	-9.00	444.72	444.83
E	237+16.25	-9.00	444.72	444.80
F	237+26.25	-9.00	444.70	444.74
⊕ Brg. N. Abut.	237+33.75	-9.00	444.69	444.69
Bk. N. Abut.	237+35.00	-9.00	444.69	444.69

**BEAM #3**

Location	Station	Offset from Ctrline	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Dead Load Deflection
Bk. S. Abut.	236+65.00	-3.00	444.76	444.76
⊕ Brg. S. Abut.	236+66.25	-3.00	444.77	444.77
A	236+76.25	-3.00	444.79	444.84
B	236+86.25	-3.00	444.80	444.90
C	236+96.25	-3.00	444.81	444.93
D	237+06.25	-3.00	444.82	444.93
E	237+16.25	-3.00	444.81	444.89
F	237+26.25	-3.00	444.80	444.84
⊕ Brg. N. Abut.	237+33.75	-3.00	444.78	444.78
Bk. N. Abut.	237+35.00	-3.00	444.78	444.78

**⊕ ROADWAY, P.G. AND STAGE CONSTRUCTION LINE**

Location	Station	Offset from Ctrline	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted for Dead Load Deflection
Bk. S. Abut.	236+65.00	0.00	444.81	444.81
⊕ Brg. S. Abut.	236+66.25	0.00	444.81	444.81
A	236+76.25	0.00	444.84	444.89
B	236+86.25	0.00	444.85	444.94
C	236+96.25	0.00	444.86	444.97
D	237+06.25	0.00	444.86	444.97
E	237+16.25	0.00	444.86	444.94
F	237+26.25	0.00	444.84	444.88
⊕ Brg. N. Abut.	237+33.75	0.00	444.83	444.83
Bk. N. Abut.	237+35.00	0.00	444.83	444.83

DESIGNED	B.G.H.
CHECKED	L.D.G.
DRAWN	K.H.L.
CHECKED	B.G.H.

Notes:  
1. Elevations are at Top of Concrete.  
2. See Sheet 5 of 23 for elevation locations.

**TOP OF SLAB ELEVATIONS**

SHEET NO. 6	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	739	1BR	GREENE	150	127
23 SHEETS	S.N. 031-0039		CONTRACT NO. 76410		
FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT					

H.M. & G. NO. 6020167