

GENERAL NOTES

- Reinforcement bars shall conform to the requirements of ASTM A 706 Gr 60. See Special Provisions.
- 2. Reinforcement bars designated (E) shall be epoxy coated.
- Layout of slope protection system may be varied in the field to suit ground conditions as directed by the Engineer.
- 4. Precast culvert alternate is not allowed.
- 5. For back filling and embankment, see Standard Specifications.
- Protective coat shall be applied to the exposed inside face and top of culvert headwalls and wingwalls.

Notch formed by rough finished board attached to and removed with formwork, each interior wall. (Do not chamfer).




LONGITUDINAL SECTION




SECTION C-C PHOEBE NESTING SITE DETAILS

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

Note:
A cantilevered sheet piling design does not appear
feasible and additional members or other retention
systems may be necessary. The Contractor shall
submit a temporary soil retention system design
including plan details and calculations for review
and acceptance by the Engineer.



TEMPORARY SOIL RETENTION SYSTEM



Existing Top slab & wall removal line - Sta. 106+52.89 Temporary support system — € culvert Temporary concrete barrier-PLAN

TEMPORARY SUPPORT SYSTEM

GENERAL NOTES, TOTAL BILL OF MATERIAL, TEMPORARY SOIL RETENTION SYSTEM, TEMPORARY SUPPORT SYSTEM STRUCTURE NO: 082-2044

TOTAL SHEET SHEETS NO. F.A.P. RTE. SECTION COUNTY SHEET NO. 2 399 243 60-(30,31,128)-1 St. Clair STRUCTURE NO: 082-2044 | CONTRACT NO. 76830 15 SHEETS FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT.

TOTAL BILL OF MATERIAL

emporary Support System L. Sum 1
itud Shear Connectors Each 186
iurnishing Soldier Piles(w section) Fooi 536
irrilling and setting Soldier piles (in soil) Cu. Ft. 3,95

Item

einforcement Bars, Epoxy Coated

pe Underdrains for Structures, 4''

emoval of Existing Structures

tone Riprap, Class A4

tructure Excavation

oncrete Structures

teel Railing, Type 2399

oncrete Box Culverts

ocomposite Wall Drain

ntreated Timber Lagging

emporary Soil Retention System

ar Splicers

ame Plates

rotective coat loor Drains

Total

169

Unit

Sq. Yd.

Pound 83,420

Cu. Yd. 270.6 Sq. Yd. 22

Each 106

Each Cu. Yd.

Foot

Each

Foot

Sg. Ft. 323

Sq. Ft. 262 Sq. Yd. 43

Each

DESIGNED - KRG CHECKED - MJK DRAWN - GSJ CHECKED - MJK

MID-AMERICA ENGINEERING SERVICES

SECTION X-X