

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000			CODE NO	ITEM	UNIT	TOTAL QUANTITIES		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	11.6	11.6								
40600300	AGGREGATE (PRIME COAT)	TON	55	55								
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	2054.8	2054.8								
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	468.9	468.9								
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	733.5	733.5								
40600990	TEMPORARY RAMP	SO YD	254.9	254.9								
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	3138.3	3138.3								
44200956	CLASS B PATCHES, TYPE II, 9 INCH	SO YD	329.9	329.9								
44213200	SAW CUTS	FOOT	1761	1761								
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	109.5	109.5								
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SO YD	7694.2	7694.2								
67100100	MOBILIZATION	L SUM	1	1								
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1								
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1								
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1								
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	46	46								
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3000	3000								
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	40537.5	40537.5								
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	500.4	500.4								
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	40537.5	40537.5								
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	187	187								
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	185	185								
Z0017202	DOWEL BARS 1 1/2"	EACH	900	900								

*\*Specialty Items*