

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000			CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000		
20200100	EARTH EXCAVATION	CU YD	38	38			X63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3	3		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5.9	5.9			67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4		
40600300	AGGREGATE (PRIME COAT)	TON	28.5	28.5			67100100	MOBILIZATION	L SUM	1	1		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	739	739			70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	540	540			70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1		
40600990	TEMPORARY RAMP	SO YD	140	140			70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1561	1561			70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4	4		
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SO YD	510	510			70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4521	4521		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	18007	18007			70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	124.8	124.8		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	189	189			70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	14055	14055		
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	74	74			70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	43	43		
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SO FT	562	562			70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	230	230		
44003100	MEDIAN REMOVAL	SO FT	8750	8750			70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	502	502		
44004250	PAVED SHOULDER REMOVAL	SO YD	534	534			X72000100	SIGN PANEL - TYPE 1	SO FT	5	5		
44200982	CLASS B PATCHES, TYPE II, 11 INCH	SO YD	98	98			X72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	8	8		
44213200	SAW CUTS	FOOT	567	567			X73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	1	1		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	9443	9443			X78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	124.8	124.8		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	21.	21			X78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	14055	14055		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	10.	10			X78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	43	43		
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SO YD	767	767			X78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	230	230		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	43	43			X78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1855	1855		
50105220	PIPE CULVERT REMOVAL	FOOT	75	75			X78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	135	135		
52100505	ANCHOR BOLTS, 5/8"	EACH	912	912			X78200300	PRISMATIC CURB REFLECTOR	EACH	148	148		
54213447	END SECTIONS 12"	EACH	3	3			X78200410	GUARDRAIL MARKERS, TYPE A	EACH	12	12		
54200217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	75	75			X78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3		
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	3	3			78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	110	110		
60500060	REMOVING INLETS	EACH	3	3			X80300100	LOCATING UNDERGROUND CABLE	FOOT	100	100		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	189	189			X88600600	DETECTOR LOOP REPLACEMENT	FOOT	2331	2331		
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SO FT	562	562			X6320100	GUARDRAIL REMOVAL SPECIAL	FOOT	102	102		
60623711	CONCRETE MEDIAN	SO FT	8750	8750			X7800100	PAINT PAVEMENT MARKING - RAISED MEDIAN	SO FT	285	285		
X63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	75	75			X7800200	PAINT PAVEMENT MARKING CURB	FOOT	597	597		
X63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	3	3									

*\*Specialty Items*

FILE NAME *	USER NAME * aifordb	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	FALL RTE. 9128	SECTION 28RS-6	COUNTY MADISON	TOTAL SHEETS 33	SHEET NO. 3
of:\pe\work\pordos\alfordb\8175070\87624-ahs-plan.dgn		DRAWN -	REVISED -							
		CHECKED -	REVISED -							
		DATE -	REVISED -							

SCALE: SHEET NO. OF SHEETS STA. TO STA. FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT