



STA 26+65 TO 26+94
(SN. 082-9951)

- ① Existing T-Beam deck
- ② Existing parapet
- ③ Existing HMA overlay 2 3/4"
- ④ Proposed Bituminous Materials (Prime Coat)
- ⑤ Proposed Aggregate (Prime Coat)
- ⑥ Proposed HMA Surface Removal - 2 1/4"
- ⑦ Proposed Leveling Binder (Machine Method), N70 - 3/4"
- ⑧ Proposed HMA Surface Course, Mix "C", N70 - 1 1/2"
- ⑨ Pavement Marking Line

| | | | | | | | | | | |
|-------------------------------------------|----------------------|------------|-----------|-----------------------------------------------------------|-------------------------------------|--------------------|---------------------|-----------|-----------------|--------------|
| FILE NAME = | USER NAME = watersle | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | TYPICAL SECTION LOCATION # 1 | F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| ci:\pw\work\pmsdot\watersle\d0175127\d876 | 885-sht-plan.dgn | DRAWN - | REVISED - | | | VAR. | DIST. 8 RES. 2010-6 | ST. CLAIR | 15 | 5 |
| PLOT SCALE = 100.0000' / IN. | | CHECKED - | REVISED - | | | CONTRACT NO. 76085 | | | | |