CONTRACT NO. 78060

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
312	101-2(RS-1,N-1)	ALEXANDER	189	29
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ENTRANCE AND SIDE ROAD

LOCATION STATION TO STATION		EXISTING ENTRANCE INFORMATION TYPE	SURFACE	INCIDENTAL HOT-MIX ASPHALT SURFACING M TON	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT) LITER	AGGERGATE (PRIME COAT) M TON	AGGREGATE BASE COURSE, TYPE A M TON	AGGEGATE SURFACE COURSE, TYPE A M TON	AGGREGATE SHOULDERS, TYPE B 150MM SQ M	GRADING AND SHAPING SPECIAL SQ M
IL 146										
RT STA 13+086.		FER	EARTH							
LT STA 3+086.		FEL	EARTH							
LT STA 3+445.		PEL	AGGREGATE					22.6		
RT STA 13+445.		FER	EARTH							
LT STA 3+572.5		FEL	EARTH							
RT STA 13+787.		FER	EARTH							
RT STA 14+079.	REIMAN RD	SRR	OIL & CHIP	68.0	545.5	0.6	193.0		73.0	
LT STA 4+079.	GERARD RD	SRL	AGGREGATE	68.0	547.5	0.6	194.0		73.0	
LT STA 4+297.		PEL	AGGREGATE					23.5		
RT STA 14+304.		FER	AGGREGATE					27.9		
RT STA 14+725.		FER	EARTH							
LT STA 4+717.		FEL	EARTH							
RT STA 14+900.		FER	EARTH							
LT STA 4+890.		FEL	EARTH							
RT STA 15+174.		FER	EARTH							
LT STA 5+175.		FEL	EARTH							
RT STA 15+550.		FER	EARTH							
LT STA 5+570.		FEL	EARTH							
RT STA 15+784.		FER	EARTH							
IL 146 PROJECT TOTAL				136.0	1,093.0	1.2	387.0	74.0	146.0	0.0
IL 3										
LT STA 41+656	REMOVE	CEL	AGGREGATE							198.0
LT STA 41+677		CEL	AGGREGATE					57.0		
RT STA 41+967	REMOVE	CER	AGGREGATE							
STA 42+220		CER	AGGREGATE					31.0		
IL 3 PROJECT TOTAL				0.0	0.0	0.0	0.0	88.0	0.0	198.0
SCHEDULE PROJECT SUB-TOTAL				136.0	1,093.0	1.2	387.0	162.0	146.0	198.0
FROM HMA RESURFACING SCHEDULE					17,286.0	54.8				
FROM HMA PAVEMENT SCHEDULE					47,046.0					
FROM SHOULDER SCHEDULE					35,333.0					
PROJECT TOTAL				136.0	100,758.0	56.0	387.0	162.0	146.0	198.0

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.

DATE

DRAWN BY JCK

CHECKED BY

PLOT DATE = 1/21/2010
FILE NAME = c:\pw_work\PWIDOT\VRANZJC\dms43640\md82599c2-sched.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kranzjc