CONTRACT NO. 78060

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
312	101-2(RS-1,N-1)	ALEXANDER	189	34
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

TEMPORARY PAVEMENT MARKINGS

LOCATION STATION TO STATION	TEMPORARY PAINT PAVEMENT MARKING								
	LINE 100MM				LINE 200MM	LINE 300MM		LINE 600MM	LETTERS AND SYMBOLS
	SOLID WHITE METER	SKIP-DASH WHITE METER	SKIP-DASH YELLOW METER	SOLID YELLOW METER	SOLID WHITE METER	SOLID WHITE METER	SOLID YELLOW METER	SOLID WHITE METER	SQ M
IL 146									
EASTBOUND									
STA 12+539.4 TO STA 12+635.6	96.2	24.4		192.4					
STA 12+635.6 TO STA 13+970.	1,334.4	332.5		1,334.4					
STA 13+970. TO STA 14+060.	180.0	21.4		90.0					
STA 14+060. TO STA 14+094.		9.2		34.0	29.0	6.0			
STA 14+094. TO STA 16+084.	1,990.0	497.2		1,990.0					
STA 16+084. TO STA 16+100.	53.3			20.5	68.4	43.2			
LT STA 14+079 RIEMAN ROAD								4.5	
LT STA 16+094.								6.0	
RT STA 16+098.								5.0	
STA 13+973. ONLY									2.0
STA 13+981.4 LT ARROW									1.5
STA 14+040. ONLY									2.0
STA 14+048.4 LT ARROW									1.5
STA 16+010. LT & RT LANES ONLY									4.0
STA 16+018.4 LT & RT LANES LT & RT ARROW									3.0
STA 16+065. LT & RT LANES ONLY									4.0
STA 16+073.4 LT & RT LANES LT & RT ARROW									3.0
WESTBOUND									
STA 2+539.4 TO STA 2+635.6	96.2	24.4		192.4			93.6		
STA 2+635.6 TO STA 4+063.5	1,427.9	356.9		1,427.9					
STA 4+063.5 TO STA 4+097.5		9.2		34.0	29.0	6.0			
STA 4+097.5 TO STA 4+187.5	180.0	21.4		90.0					
STA 4+187.5 TO STA 6+006.	1,818.5	454.5		1,818.5					
STA 6+006. TO STA 6+100.				88.8	94.0	27.2			
RT STA 4+079 GERARD ROAD								4.5	
STA 4+108.6 LT ARROW									1.5
STA 4+117. ONLY									2.0
STA 4+175.6 LT ARROW									1.5
STA 4+184. ONLY									2.0
RAMP									
STA 0+000. TO STA 0+133.6	133.9				133.6				
IL 146 PROJECT SUB-TOTALS	7,310.4	1,750.7	0.0	7,312.9		82.4	93.6		
IL 146 PROJECT TOTALS		16,374.0			354.0	176.0		20.0	28.0
IL 3									
STA 41+623.6 TO STA 41+653.6	60.0		6.1						
STA 41+653.6 TO STA 41+858.6	410.0			820.0			108.0		
STA 41+858.6 TO STA 41+904.7	138.2			184.3			16.0		
STA 41+904.7 TO STA 41+933.8	58.2			116.5			10.0		
STA 41+933.8 TO STA 41+941.7	7.9			31.6			1.6		
STA 41+941.7 TO STA 41+971.8	30.1								
STA 41+971.8 TO STA 42+054.3	82.5			330.0	83.0	44.7	70.5		
STA 42+054.3 TO STA 42+108.8	163.5			218.0			14.2		
STA 42+108.8 TO STA 42+120.	33.6			22.4					
STA 42+120. TO STA 42+205.	170.0			170.0					
STA 42+205. TO STA 42+225.	40.0		6.1						
STA 41+861.6 ONLY									2.0
STA 41+867.6 LT ARROW									1.5
STA 41+915. ONLY									2.0
STA 41+921. LT ARROW									1.5
STA 42+111. RT ARROW									1.5
STA 42+117. ONLY									2.0
IL 3 SUB-TOTALS	1,194.0	0.0	12.2	1,892.8		44.7	220.3		
IL 3 TOTALS		3,099.0			83.0	265.0		0.0	10.5
PROJECT SUB-TOTALS	8,504.4	1,750.7	12.2	9,205.7		127.1	313.9		
PROJECT TOTALS		19,473.0			437.0	441.0		20.0	38.5

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.

DATE

DRAWN BY JCK

CHECKED BY

PLOT DATE = 9/14/2009
FILE NAME = c:\pwworking\PWIDOT\KRANZJC\dms43640\sm8025995c2-schedul.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kranzjc