

SUMMARY OF QUANTITIES				80% FED, 20% STATE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODES	
				I000-2A	X571-2A
20100500	TREE REMOVAL, ACRES	ACRE	0.25	0.25	
20200100	EARTH EXCAVATION	CU YD	1,016	1,016	
20400800	FURNISHED EXCAVATION	CU YD	3,282	3,282	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	346		346
20900110	POROUS GRANULAR BACKFILL	CU YD	471	471	
25000210	SEEDING, CLASS 2A	ACRE	1.75	1.75	
25000350	SEEDING, CLASS 7	ACRE	1.75	1.75	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	158	158	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	158	158	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	158	158	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	3.5	3.5	
25100115	MULCH, METHOD 2	ACRE	1.75	1.75	
25100630	EROSION CONTROL BLANKET	SQ YD	3,794	3,794	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	525	525	
28000305	TEMPORARY DITCH CHECKS	FOOT	48	48	
28000400	PERIMETER EROSION BARRIER	FOOT	5,727	5,727	
28000500	INLET AND PIPE PROTECTION	EACH	14	14	
28100105	STONE RIPRAP, CLASS A3	SQ YD	102	8	94
28200200	FILTER FABRIC	SQ YD	102	8	94
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	12,278	12,278	

SUMMARY OF QUANTITIES				80% FED, 20% STATE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODES	
				I000-2A	X571-2A
30201500	LIME	TON	236.3	236.3	
31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	1,674	1,674	
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3,345	3,345	
40600300	AGGREGATE (PRIME COAT)	TON	46	46	
40600895	CONSTRUCTING TEST STRIP	EACH	4	4	
40600990	TEMPORARY RAMP	SQ YD	144	144	
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	7,207	7,207	
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	4,239	4,239	
40603575	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N105	TON	2,130	2,130	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	174	174	
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	814	814	
42001300	PROTECTIVE COAT	SQ YD	2,832	2,832	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	400	400	
44000100	PAVEMENT REMOVAL	SQ YD	400	400	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	30,117	30,117	
44000700	APPROACH SLAB REMOVAL	SQ YD	415	415	
44004250	PAVED SHOULDER REMOVAL	SQ YD	3,217	3,217	
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	298	298	
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	20	20	
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	153	153	

* SPECIALTY ITEM

FILE NAME =	USER NAME = moisiugrosser	DESIGNED -	REVISED -
H:\VP\25086p2\Technical_Production\Civil\	florostation\Sec285VB\Sof0285vb.dgn	DRAWN -	REVISED -
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/15/2010	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES	
I-57 OVER 7TH ST / C&E1 RAILROAD	
SCALE:	SHEET NO. 1 OF 3 SHEETS
STA.	TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(28-5)VB-1	FRANKLIN	81	4
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 78157	