

SUMMARY OF QUANTITIES				80% FED, 20% STATE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODES	
				I000-2A	X571-2A
44201294	CLASS B PATCH - EXPANSION JOINT	FOOT	504	504	
44213100	PAVEMENT FABRIC	SQ YD	173	173	
44213200	SAW CUTS	FOOT	2,063	2,063	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	283	283	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1,275	1,275	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	2		2
50105220	PIPE CULVERT REMOVAL	FOOT	54	54	
50157300	PROTECTIVE SHIELD	SQ YD	373		373
50200100	STRUCTURE EXCAVATION	CU YD	275		275
50300100	FLOOR DRAINS	EACH	16		16
50300225	CONCRETE STRUCTURES	CU YD	369.1		369.1
50300255	CONCRETE SUPERSTRUCTURE	CU YD	780.5		780.5
50300260	BRIDGE DECK GROOVING	SQ YD	3,126	768	2,358
50300280	CONCRETE ENCASEMENT	CU YD	29.4		29.4
50300300	PROTECTIVE COAT	SQ YD	2,796		2,796
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	9,900		9,900
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	186,390		186,390
50800515	BAR SPLICERS	EACH	1,358		1,358
51100100	SLOPE WALL 4 INCH	SQ YD	1,451		1,451

SUMMARY OF QUANTITIES				80% FED, 20% STATE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODES	
				I000-2A	X571-2A
51201600	FURNISHING STEEL PILES HP12X53	FOOT	5,175		5,175
51201610	FURNISHING STEEL PILES HP12X63	FOOT	3,193		3,193
51202305	DRIVING PILES	FOOT	8,368		8,368
51203600	TEST PILE STEEL HP12X53	EACH	2		2
51203610	TEST PILE STEEL HP12X63	EACH	1		1
51204650	PILE SHOES	EACH	84		84
51205200	TEMPORARY SHEET PILING	SQ FT	368		368
51500100	NAME PLATES	EACH	2		2
52000030	PREFORMED JOINT SEAL 2 1/2"	FOOT	184.5		184.5
52100520	ANCHOR BOLTS, 1"	EACH	132		132
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	975	975	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	199		199
60107600	PIPE UNDERDRAINS 4"	FOOT	3,950	3,950	
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	115	115	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	317		317
60270055	DRAINAGE STRUCTURES, TYPE 5 WITH TWO TYPE 22 FRAME AND GRATES	EACH	7	7	
60500060	REMOVING INLETS	EACH	2	2	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FT. POSTS	FOOT	4,375.0	4,375.0	
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1	
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	2	2	

* SPECIALTY ITEM

FILE NAME =	USER NAME = malsiegraser	DESIGNED -	REVISED -
H:\P\25866p2\Technical_Production\Civil\	microstation\Sec285VB\Sec0285vb.dgn	DRAWN -	REVISED -
	PLOT SCALE = 5/8" = 1" IN.	CHECKED -	REVISED -
	PLOT DATE = 3/15/2018	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
I-57 OVER 7TH ST / C&E RAILROAD			
SCALE:	SHEET NO. 2 OF 3 SHEETS	STA.	TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(28-5)VB-1	FRANKLIN	81	5
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 78157	