

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY J000
* 20200100	EARTH EXCAVATION	CU YD	4,241
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	570
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2,912
25000110	SEEDING, CLASS 1A	ACRE	0.6
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	54
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	54
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	54
25100630	EROSION CONTROL BLANKET	SQ YD	2,912
28000500	INLET AND PIPE PROTECTION	EACH	52
28000510	INLET FILTERS	EACH	52
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	60
* 31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	390
35101400	AGGREGATE BASE COURSE, TYPE B	TON	1,472
35400100	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 6"	SQ YD	54
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	38
* 40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	200
* 40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	172
40600990	TEMPORARY RAMP	SQ YD	150
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	91
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	72
* 42000900	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	830
42001300	PROTECTIVE COAT	SQ YD	5,863
* 42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	428
* 42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	644
* 42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	4,270
* 42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	649
* 42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	1,381
42400800	DETECTABLE WARNINGS	SQ FT	96
44000100	PAVEMENT REMOVAL	SQ YD	86
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	359
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	290
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	145
44000600	SIDEWALK REMOVAL	SQ FT	1,186
* 48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	134
* 56300100	ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS	FOOT	100
* 60255500	MANHOLES TO BE ADJUSTED	EACH	1
* 60266600	VALVE BOXES TO BE ADJUSTED	EACH	17
* 60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	2,772

△ SPECIALTY ITEM
* SPECIAL PROVISION

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY J000
* 60604800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18 (SPECIAL)	FOOT	208
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	2
61133200	FIELD TILE JUNCTION VAULTS, 3' DIA.	EACH	2
61139800	STORM SEWERS, SPECIAL 4"	FOOT	100
61139900	STORM SEWERS, SPECIAL 6"	FOOT	100
61140000	STORM SEWERS, SPECIAL 8"	FOOT	100
61140100	STORM SEWERS, SPECIAL 10"	FOOT	100
67100100	MOBILIZATION	L SUM	1
* 70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
* 72000100	SIGN PANEL - TYPE 1	SQ FT	22
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	27
△ 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	1,279
△ 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	375
△ 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	108
△ 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	181
* LR420029	PORTLAND CEMENT CONCRETE PAVEMENT 8" (SPECIAL)	SQ YD	4,343
* X0932150	CURB AND GUTTER OUTLET, SPECIAL	EACH	12

p:\c\1\2\05_pontiac\2009\080539_Sum-Quant.dgn

FILE NAME = 080539_Sum-Quant.dgn	USER NAME = #USER#	DESIGNED - DWR/JDA	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	CITY OF PONTIAC - AURORA STREET (FAU 6319) SUMMARY OF QUANTITIES			F.A.U. RTE. 6319	SECTION 08-00091-00-RP	COUNTY LIVINGSTON	TOTAL SHEETS 31	SHEET NO. 2
PLOT SCALE = #SCALE#	CHECKED - ERB	REVISIED -	REVISIED -		SCALE: N.T.S.	SHEET NO. OF	SHEETS	STA. 10+18	TO STA. 25+59.5	FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT		
PLOT DATE = 3/25/2010	DATE - 03/25/10	REVISIED -	REVISIED -					CONTRACT NO. 87404				
								<small>301 W. WASHINGTON STREET, PONTIAC, IL 61764 (815) 844-5571 / (815) 844-3147 FAX www.f-w.com</small>				