

0081364_Sum-Quant.dgn 11/21/15 AM 3/9/2010
P:\2008\0081364\0081364.dwg

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY I000	NON-PARTICIPATING Y060
20200100	EARTH EXCAVATION	CU YD	1,953	
* 20201500	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	850	
* 20800150	TRENCH BACKFILL	CU YD	100	
* 21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1,250	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3,245	
25000100	SEEDING, CLASS 1	ACRE	0.7	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	63	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	63	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	63	
25100630	EROSION CONTROL BLANKET	SQ YD	3,245	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	134	
28000500	INLET AND PIPE PROTECTION	EACH	51	
28000510	INLET FILTERS	EACH	27	
35100100	AGGREGATE BASE COURSE, TYPE A	TON	3,590	
* 40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	600	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3,568	
40600300	AGGREGATE (PRIME COAT)	TON	13	
40600990	TEMPORARY RAMP	SQ YD	235	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	928	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	618	
42001300	PROTECTIVE COAT	SQ YD	586	
* 42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	103	
* 42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	106	
* 42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	1,330	
* 42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	125	
42400800	DETECTABLE WARNINGS	SQ FT	82	
44000100	PAVEMENT REMOVAL	SQ YD	6,533	
44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SQ YD	581	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	161	
44000300	CURB REMOVAL	FOOT	2,793	
44000400	GUTTER REMOVAL	FOOT	15	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	44	
44000600	SIDEWALK REMOVAL	SQ FT	1,280	
* 44201474	CLASS C PATCHES, TYPE I	SQ YD	3	
* 44201476	CLASS C PATCHES, TYPE II	SQ YD	11	
* 44201478	CLASS C PATCHES, TYPE III	SQ YD	38	
* 44201480	CLASS C PATCHES, TYPE IV	SQ YD	1,259	
* 44201980	CLASS D PATCHES, TYPE IV	SQ YD	94	

△ SPECIALTY ITEM
* SPECIAL PROVISION

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY I000	NON-PARTICIPATING Y060
550A5300	STORM SEWERS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 36"	FOOT	106	
550B0050	STORM SEWERS, CLASS B, TYPE 1 12"	FOOT	260	
550B0340	STORM SEWERS, CLASS B, TYPE 2 12"	FOOT	218	
550B0360	STORM SEWERS, CLASS B, TYPE 2 15"	FOOT	52	
550B0380	STORM SEWERS, CLASS B, TYPE 2 18"	FOOT	50	
550B0410	STORM SEWERS, CLASS B, TYPE 2 24"	FOOT	20	
550B0430	STORM SEWERS, CLASS B, TYPE 2 30"	FOOT	525	
550B0450	STORM SEWERS, CLASS B, TYPE 2 36"	FOOT	1,585	
550B0730	STORM SEWERS, CLASS B, TYPE 3 30"	FOOT	93	
550B0750	STORM SEWERS, CLASS B, TYPE 3 36"	FOOT	268	
* X0321905	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE 12"	FOOT	120	
* X0323093	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE 24"	FOOT	240	
* X0321907	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE 12"	FOOT	134	
* X0323954	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE 18"	FOOT	22	
* X0321909	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE 24"	FOOT	156	
* X0321912	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE 30"	FOOT	83	
△* 56100700	WATER MAIN 8"	FOOT		855
△* XX008209	TAPPING VALVES AND SLEEVES 10" X 8"	EACH		2
△* XX008233	MJ CAPS, 4"	EACH		2
△* XX008234	MJ CAPS, 8"	EACH		1
△* 56200300	WATER SERVICE LINE 1"	FOOT		166
△* 56300100	ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS	FOOT	150	
△* 56300300	ADJUSTING WATER SERVICE LINES	FOOT	100	
△* 56400500	FIRE HYDRANTS TO BE REMOVED	EACH		2
△* 56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH		2
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	130	
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	
60221000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	19	
60223700	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	3	
* 60231700	MANHOLES, SPECIAL, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	
* X0301007	INLET-MANHOLE, TYPE G-1, 4'-DIAMETER, SPECIAL	EACH	1	
60237000	INLETS, TYPE A, TYPE 15 FRAME AND LID	EACH	1	
* 60241800	INLETS, TYPE G-1	EACH	25	
* 60255500	MANHOLES TO BE ADJUSTED	EACH	2	
60500040	REMOVING MANHOLES	EACH	2	
60500060	REMOVING INLETS	EACH	15	
* 60600605	CONCRETE CURB, TYPE B	FOOT	129	
* 60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2,476	

FILE NAME = 0081364-Sum-Quant.dgn	USER NAME =	DESIGNED - PSA	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	CITY OF HAVANA - BROADWAY STREET SUMMARY OF QUANTITIES				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - JTC	REVISED -							05-00035-00-SS	MASON	36	2
	PLOT SCALE =	CHECKED - ERB	REVISED -						CONTRACT NO. 93502				
	PLOT DATE = 3/9/2010 11:21:15 AM	DATE - 03/09/10	REVISED -						FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
				SCALE: N.T.S.	SHEET NO.	OF	SHEETS	STA. 23+45	TO STA. 55+75				