

CONCRETE

LOCATION	PROTECTIVE COAT (SQ YD)	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (FOOT)	CONCRETE CURB, TYPE B (FOOT)	CURB REMOVAL (FOOT)	GUTTER REMOVAL (FOOT)	COMBINATION CURB AND GUTTER REMOVAL (FOOT)	PAVEMENT REMOVAL (SQ YD)
STA. 24+02.00 TO 27+33.00	282	1,220		1,280			1,377
STA. 27+96.00 TO 31+77.61	285	1,230		1,267			1,422
STA. 31+77.61 TO 36+27.50							
STA. 36+27.50 TO 39+85.52							723
STA. 39+85.52 TO 43+83.75							790
STA. 43+83.75 TO 47+52.87							733
STA. 47+52.87 TO 52+11.25							897
STA. 52+11.25 TO 55+12.00							591
STA. 23+55.00, RT.	1	6				6	
STA. 27+49.00, RT.						9	
STA. 27+79.00, RT.						9	
STA. 27+90.00, RT.	5	20				20	
STA. 28+13.00, RT.					15		
STA. 31+42.00, RT.				9			
STA. 32+12.00, RT.				9			
STA. 34+19.00, RT.	1		10	10			
STA. 34+60.00, LT.	2		15	15			
STA. 38+45.00, LT.	1		12	21			
STA. 39+44.00, LT.				9			
STA. 41+72.00, LT.	1		12	21			
STA. 43+48.00, LT.	1		6	15			
STA. 45+35.00, LT.	1		12	21			
STA. 46+95.00, LT.	1		12	12			
STA. 47+10.00, LT.				9			
STA. 47+95.00, LT.				9			
STA. 48+00.00, LT.	1		12	12			
STA. 49+75.00, LT.	1		12	21			
STA. 51+85.00, RT.	1		10	19			
STA. 52+30.00, RT.				9			
STA. 54+67.73, LT.	2		16	25			
TOTALS	586	2,476	129	2,793	15	44	6,533

BITUMINOUS MATERIALS

LOCATION	AGGREGATE BASE COURSE, TYPE A (8") (TON)	BITUMINOUS MATERIALS (PRIME COAT) (GAL)		AGGREGATE (PRIME COAT) (TON)	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 (TON)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 (TON)
		MC-30	RC-70			
STA. 23+68.21 TO 27+63.63	743	653	164	3	212	141
STA. 27+63.63 TO 31+26.00	762	660	168	3	218	145
STA. 31+26.00 TO 36+27.50						
STA. 36+27.50 TO 39+85.52	324	285	71	1	92	61
STA. 39+85.52 TO 43+83.75	360	316	79	2	102	68
STA. 43+83.75 TO 47+52.87	333	292	73	1	95	63
STA. 47+52.87 TO 52+11.25	409	359	90	2	116	78
STA. 52+11.25 TO 55+75.00	326	286	72	1	93	62
TOTALS	3,257	2,861	717	13	928	618

HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"

LOCATION	SQ YD
STA. 27+28.00 TO STA. 28+00.00	581
TOTAL	581

CONTROLLED LOW-STRENGTH MATERIAL

LOCATION	CU YD
STA. 55+62.00, 19.0' LT.	130
TOTAL	130

PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH

LOCATION	WIDTH (FOOT)	WIDTH @ CURB (FOOT)	LENGTH (FOOT)	SQ YD
STA. 25+26.50, LT.	12.0	14.5	11.5	17
STA. 25+86.50, LT.	12.0	18.0	12.0	20
STA. 28+55.50, RT.	12.0	14.0	15.0	22
STA. 28+84.00, RT.	12.0	14.0	15.0	22
STA. 29+87.50, RT.	12.0	14.0	15.0	22
TOTAL				103

PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH

LOCATION	WIDTH (FOOT)	WIDTH @ CURB (FOOT)	LENGTH (FOOT)	SQ YD
STA. 25+97.00, RT.	12.0	25.0	14.0	27
STA. 26+72.50, RT.	12.0	22.0	13.5	26
STA. 30+15.00, LT.	25.0	45.0	13.5	53
TOTAL				106

DRIVEWAY PAVEMENT REMOVAL

LOCATION	SQ YD
STA. 25+26.50, LT.	15
STA. 25+86.50, LT.	15
STA. 25+97.00, RT.	22
STA. 28+55.50, RT.	16
STA. 28+84.00, RT.	18
STA. 29+87.50, RT.	18
STA. 30+15.00, LT.	57
TOTAL	161

TEMPORARY RAMP

LOCATION	SQ. YD.
STA. 24+02.00	31
STA. 27+63.63, LT.	16
STA. 27+63.63, RT.	14
STA. 31+26.00	20
STA. 36+27.50, LT.	10
STA. 39+85.52, LT.	19
STA. 39+85.52, LT.	19
STA. 43+83.75, LT.	17
STA. 43+83.75, LT.	19
STA. 47+52.87, LT.	16
STA. 47+52.87, LT.	19
STA. 52+11.25, LT.	19
STA. 55+46.49, LT.	16
STA. 55+46.49, LT.	22
STA. 55+75.00, LT.	9
TOTAL	235

CONCRETE STEPS

LOCATION	SQ FT
STA. 24+99.00, RT.	39
TOTAL	39

DETECTABLE WARNINGS

LOCATION	SQ FT
STA. 24+27.30, LT.	4
STA. 24+99.00, RT.	10
STA. 27+34.00, RT.	8
STA. 27+48.00, RT.	8
STA. 29+02.80, RT.	8
STA. 29+61.00, RT.	8
STA. 29+61.00, RT.	8
STA. 30+43.50, RT.	28
TOTAL	82

SIDEWALK REMOVAL

LOCATION		SQ FT
STA. 23+99.00, LT.	TO STA. 24+11.40, LT.	65
STA. 24+25.30, LT.	TO STA. 24+29.30, LT.	19
STA. 24+85.00, LT.	TO STA. 24+90.00, LT.	20
STA. 24+96.20, RT.	TO STA. 25+01.20, RT.	64
STA. 25+33.70, RT.	TO STA. 25+88.50, RT.	205
STA. 25+70.70, LT.	TO STA. 25+74.70, LT.	34
STA. 25+92.50, LT.	TO STA. 25+97.50, LT.	20
STA. 26+49.80, RT.	TO STA. 26+54.80, RT.	25
STA. 26+61.00, LT.	TO STA. 26+66.00, LT.	21
STA. 27+00.25, LT.	TO STA. 27+11.50, LT.	51
STA. 27+31.00, RT.	TO STA. 27+48.60, RT.	174
STA. 28+15.80, LT.	TO STA. 28+20.80, LT.	26
STA. 28+40.00, RT.	TO STA. 28+47.20, RT.	28
STA. 28+68.00, RT.	TO STA. 28+78.00, RT.	41
STA. 29+00.75, RT.	TO STA. 29+04.75, RT.	52
STA. 29+21.50, LT.	TO STA. 29+26.50, LT.	26
STA. 29+51.10, RT.	TO STA. 29+68.10, RT.	72
STA. 29+76.10, RT.	TO STA. 29+81.50, RT.	20
STA. 30+04.50, RT.	TO STA. 30+96.80, RT.	317
TOTAL		1,280

PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH

LOCATION		SQ FT
STA. 23+99.00, LT.	TO STA. 24+11.40, LT.	65
STA. 24+25.30, LT.	TO STA. 24+29.30, LT.	44
STA. 24+85.00, LT.	TO STA. 24+90.00, LT.	20
STA. 24+96.20, RT.	TO STA. 25+01.20, RT.	30
STA. 25+33.70, RT.	TO STA. 25+88.50, RT.	205
STA. 25+70.70, LT.	TO STA. 25+74.70, LT.	46
STA. 25+92.50, LT.	TO STA. 25+97.50, LT.	20
STA. 26+49.80, RT.	TO STA. 26+54.80, RT.	25
STA. 26+61.00, LT.	TO STA. 26+66.00, LT.	21
STA. 27+00.25, LT.	TO STA. 27+11.50, LT.	51
STA. 27+31.00, RT.	TO STA. 27+48.60, RT.	174
STA. 28+15.80, LT.	TO STA. 28+20.80, LT.	26
STA. 28+40.00, RT.	TO STA. 28+47.20, RT.	28
STA. 28+68.00, RT.	TO STA. 28+78.00, RT.	41
STA. 29+00.75, RT.	TO STA. 29+04.75, RT.	62
STA. 29+21.50, LT.	TO STA. 29+26.50, LT.	26
STA. 29+51.10, RT.	TO STA. 29+68.10, RT.	102
STA. 29+76.10, RT.	TO STA. 29+81.50, RT.	20
STA. 30+04.50, RT.	TO STA. 30+96.80, RT.	324
TOTAL		1,330

PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH

LOCATION		SQ FT
STA. 30+02.50, LT.	TO STA. 30+27.50, LT.	125
TOTAL		125

BRICK PAVER REMOVAL AND REPLACEMENT

LOCATION		SQ FT
STA. 31+28.11, LT.	TO STA. 31+33.66, LT.	104
STA. 31+28.11, RT.	TO STA. 31+33.66, RT.	45
STA. 32+20.72, LT.	TO STA. 32+26.55, LT.	107
TOTAL		256

CONCRETE HEADER BAND

LOCATION		FOOT
STA. 31+26.00, RT.	TO STA. 31+26.00, RT.	8
STA. 31+26.00, LT.	TO STA. 31+28.00, LT.	18
TOTAL		26

TAPPING VALVES AND SLEEVES 10" x 8"

LOCATION	EACH
STA. 23+72.00, 30.5' RT.	1
STA. 31+99.50, 23.0' RT.	1
TOTAL	2

MJ CAPS, 4"

LOCATION	EACH
STA. 23+79.50, 19.0' RT.	1
STA. 31+86.00, 16.5' RT.	1
TOTAL	2

MJ CAPS, 8"

LOCATION	EACH
STA. 23+45.00, 29.5' RT.	1
TOTAL	1

FIRE HYDRANTS TO BE REMOVED

LOCATION	EACH
STA. 24+01.50, 37.0' RT.	1
STA. 27+88.50, 39.0' LT.	1
TOTAL	2

FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX

LOCATION	EACH
STA. 24+08.00, 23.0' RT.	1
STA. 27+87.00, 23.0' RT.	1
TOTAL	2

GATE VALVES, 8"

LOCATION	EACH
STA. 23+70.50, 26.0' RT.	1
STA. 27+83.40, 23.0' RT.	1
TOTAL	2

DUCTILE IRON WATER MAIN FITTINGS, 8" 45 DEGREE BEND

LOCATION	EACH
STA. 23+77.00, 31.0' RT.	1
STA. 23+80.00, 28.0' RT.	1
TOTAL	2

DUCTILE IRON WATER MAIN TEE, 8" x 8"

LOCATION	EACH
STA. 23+65.00, 23.0' RT.	1
TOTAL	1

WATER MAIN 8"

LOCATION		FOOT
STA. 23+45.00	TO STA. 27+63.63	418
STA. 27+63.63	TO STA. 32+00.00	437
TOTAL		855

WATER SERVICE LINE 1"

LOCATION	FOOT
STA. 25+22.00, RT.	18
STA. 25+86.50, RT.	14
STA. 26+52.00, RT.	19
STA. 27+39.00, RT.	28
STA. 28+42.50, RT.	21
STA. 28+73.00, RT.	27
STA. 29+78.50, RT.	21
STA. 31+01.00, RT.	18
TOTAL	166

WATER SERVICE LINE 1", BORED

LOCATION	FOOT
STA. 24+08.50, LT.	62
STA. 24+86.00, LT.	62
STA. 25+87.00, LT.	64
STA. 26+62.50, LT.	64
STA. 27+03.00, LT.	64
STA. 28+17.00, LT.	65
STA. 29+23.00, LT.	65
TOTAL	446

CONNECTION TO EXISTING WATERMAIN

LOCATION	EACH
STA. 23+72.00, 30.5' RT.	1
STA. 31+99.50, 23.0' RT.	1
TOTAL	2

WATER SERVICE CONNECTION 1"

LOCATION	EACH
STA. 24+08.50, LT.	1
STA. 24+86.00, LT.	1
STA. 25+22.00, RT.	1
STA. 25+86.50, RT.	1
STA. 25+87.00, LT.	1
STA. 26+62.00, RT.	1
STA. 26+62.50, LT.	1
STA. 27+03.00, LT.	1
STA. 27+39.00, RT.	1
STA. 28+17.00, LT.	1
STA. 28+42.50, RT.	1
STA. 28+73.00, RT.	1
STA. 29+23.00, LT.	1
STA. 29+78.50, RT.	1
STA. 31+01.00, RT.	1
TOTAL	15