STA 23+68.21 BK. BROADWAY STREET=
STA 400+00.00 WASHINGTON STREET

IMROVEMENTS BEGIN
STA 23+45.0

EX ROW

STA 23+68.21 AHD.
BROADWAY STREET =
STA 400+06.21
WASHINGTON STREET

SCALE IN FEET
20 0 20

21 22 23 24 25+00

BROADWAY STREET

WASHINGTON STREET

MATCH LINE STA 26+00

LEGEND
INLET & PIPE PROTECTION
PROPOSED DRAINAGE ARROW

NOTE:
1. INLET FILTERS SHALL BE PLACED IN EACH CURB INLET AND MAINTAINED UNTIL PERMANENT SEEDING IS ESTABLISHED TO THE SATISFACTION OF THE CITY AND ENGINEER.
2. SEE SECTIONS 250 AND 251 OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, JANUARY 1, 2007, STORM WATER POLLUTION PREVENTION PLAN, AND PROVISIONS OF THE NPDES PERMIT NUMBER ILR10 FOR TEMPORARY AND PERMANENT SEEDING, DUST CONTROL AND CLEANING OF PAVEMENT AS NECESSARY.

STA 27+63.63 BROADWAY STREET=
℄ ADAMS STREET

ADAMS STREET

SCALE IN FEET
20 0 20

4" PVC

STA 31+77.61
BROADWAY STREET=
℄ MAIN STREET

MATCH LINE STA 26+00

26 27 28 29 30+00 31

BROADWAY STREET

MAIN STREET

MATCH LINE STA 32+00

LEGEND
INLET & PIPE PROTECTION
PROPOSED DRAINAGE ARROW

NOTE:
1. INLET FILTERS SHALL BE PLACED IN EACH CURB INLET AND MAINTAINED UNTIL PERMANENT SEEDING IS ESTABLISHED TO THE SATISFACTION OF THE CITY AND ENGINEER.
2. SEE SECTIONS 250 AND 251 OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, JANUARY 1, 2007, STORM WATER POLLUTION PREVENTION PLAN, AND PROVISIONS OF THE NPDES PERMIT NUMBER ILR10 FOR TEMPORARY AND PERMANENT SEEDING, DUST CONTROL AND CLEANING OF PAVEMENT AS NECESSARY.

0081364_EROSION11.dgn
3/9/2010 11:23:55 AM
p:/2008/0081364_Havana_Broadway/dgn/

FILE NAME = 0081364_EROSION11.dgn	USER NAME =	DESIGNED - PSA	REVISED -
		DRAWN - JTC	REVISED -
	PLOT SCALE =	CHECKED - ERB	REVISED -
	PLOT DATE = 3/9/2010 11:23:55 AM	DATE - 03/09/10	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

CITY OF HAVANA – BROADWAY STREET
EROSION CONTROL PLAN "SWPPP"

SCALE: 1" = 20' | SHEET NO. OF SHEETS | STA. 20+50 | TO STA. 32+00

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	05-00035-00-SS	MASON	36	19
		CONTRACT NO. 93502		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

Farnsworth GROUP
1707 NORTH KNOXVILLE AVENUE, SUITE 200, PEORIA, ILLINOIS 61614
(309)689-9888 / (309)689-9820 FAX
www.f-w.com