

MODEL: Default
FILE NAME: prj\planroom dot illinois gov-PWD\DOT\Documents\DOT Office\District 3\project\03366668\CADD\data\CAD\sheet\03366668-sh-500.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				FUND CODE NHPP	FUND CODE NHPP
				ROADWAY	ROADWAY
				0005	0005
				URBAN	RURAL
20400800	FURNISHED EXCAVATION	CU YD	75	20	55
20700220	POROUS GRANULAR EMBANKMENT	CU YD	70		70
21400100	GRADING AND SHAPING DITCHES	FOOT	2410		2410
25000200	SEEDING, CLASS 2	ACRE	0.25		0.25
28100107	STONE RIPRAP, CLASS A4	SQ YD	77		77
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	43	2	41
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	118159	7096	111063
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	51.3	2.8	48.5
40600990	TEMPORARY RAMP	SQ YD	1132	380	752
40604052	HOT-MIX ASPHALT SURFACE COURSE, 1L-9.5, MIX "C", N70	TON	14348	797	13551
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	714	175	539
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	1701	1701	
42400800	DETECTABLE WARNINGS	SQ FT	335	335	
44000100	PAVEMENT REMOVAL	SQ YD	29	29	

*= SPECIALTY ITEM

	USER NAME = NOLASCOCJ	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					326	(123,123X)R3-4&(124)R5-6,SW	LIVINGSTON	27	3
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED +					CONTRACT NO. 66K86				
	PLOT DATE = 3/24/2021	DATE -	REVISED +					ILLINOIS FED. AID PROJECT				
SCALE:		SHEET	OF	SHEETS	STA.	TO STA.						

MODEL: Default
FILE NAME: p:\p1\p1anscom dot illinois.gov-p\W\DOT\Documents\DOT Office\District 3\project\03366668\CADD\data\CAD\sheet\03366668-sh-500.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				FUND CODE NHPP	FUND CODE NHPP
				ROADWAY	ROADWAY
				0005	0005
				URBAN	RURAL
44000155	HOT-MIX ASPHALT SURFACE REMOVAL , 1 1/2"	SQ YD	170796	9480	161316
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	175	175	
44000600	SIDEWALK REMOVAL	SQ FT	1558	1558	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1808		1808
56109210	WATER VALVES TO BE ADJUSTED	EACH	8	8	
56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	1	1	
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	12	12	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	150	150	
63500105	DELINEATORS	EACH	14		14
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	96184		96184
* 66700205	PERMANENT SURVEY MARKERS, TYPE 1	EACH	21		21
* 66900105	UNDERGROUND STORAGE TANK REMOVAL	EACH	1	1	
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	335	10	325
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	5	1	4

*= SPECIALTY ITEM

	USER NAME = NOLASCOCJ	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					326	(123,123X)R3-4&(124)RS-6,SW	LIVINGSTON	27	4
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED +					CONTRACT NO. 66K86				
	PLOT DATE = 3/24/2021	DATE -	REVISED +		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	

MODEL Default
FILE Name: prj\planroom dot illinois gov\p\W\DOT\Documents\DOT Office\District 3\project\03366668\CADD\data\CAD\sheet\03366668-sh-500.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				FUND CODE NHPP	FUND CODE NHPP
				ROADWAY	ROADWAY
				0005	0005
				URBAN	RURAL
*	66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	L SUM 1	0.03	0.97
*	66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	L SUM 1	0.03	0.97
*	66901006	REGULATED SUBSTANCES MONITORING	CAL DA 7	1	6
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO 4	1	3
	67100100	MOBILIZATION	L SUM 1	0.04	0.96
	70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM 1	0.04	0.96
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM 1	1	
	70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM 1	1	
	70300100	SHORT TERM PAVEMENT MARKING	FOOT 7235	307	6928
	70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT 2410	103	2307
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT 108	61	47
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT 6570	1164	5406
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT 3777	1226	2551
*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT 260		260

*= SPECIALTY ITEM

	USER NAME = NOLASCOCJ	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -						326	(123,123X)R3-46(124)RS-6,SW	LIVINGSTON	27	5
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED +						CONTRACT NO. 66K86				
	PLOT DATE = 3/24/2021	DATE -	REVISED +		ILLINOIS FED. AID PROJECT								
	SCALE: SHEET OF SHEETS STA. TO STA.				REV. 5/24/21 REV. 4/20/21 REV. 3/30/21								

MODEL: Default
FILE NAME: pw:\planroom.dot; illinois.gov\FWIDOT\Documents\DOT_Offices\District_31\Projects\31366K816-sht-S00.dgn

				CONSTRUCTION CODE	
				FUND CODE NHPP	FUND CODE NHPP
				ROADWAY	ROADWAY
				0005	0005
				URBAN	RURAL
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	386	216	170
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	222092		222092
78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	23360		23360
78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	39	39	
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	645	27	618
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	644	26	618
X0320050	CONSTRUCTION LAYOUT (SPECIAL)	L SUM	1	1	
X0324894	WATERMAIN MANHOLES TO BE ADJUSTED	EACH	1	1	
X0326341	REATTACH END SECTION	EACH	2		2
X0327809	LINEAR DELINEATOR PANELS, 4 INCH	EACH	65		65
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	6364	1544	4820
X6300222	CONNECTING END SECTION	EACH	1		1
X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	6570	1164	5406
X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	3757	1206	2551
X7830076	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	260		260
X7830090	GROOVING FOR RECESSED PAVEMENT MARKING 25"	FOOT	39	39	

*= SPECIALTY ITEM

	USER NAME = NOLASCOCJ	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -						326	(123,123X)R3-4&(124)R5-6,5W	LIVINGSTON	27	6
	PLOT SCALE = 100.0000 " / in.	CHECKED -	REVISED -		CONTRACT NO. 66K86								
	PLOT DATE = 3/24/2021	DATE -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.			

MODEL: Default
FILE NAME: p:\v\lalamroom\dot.illinois.gov\PWIDOT\Documents\IDOT Office\District 3\Projects\ID366K86\CADData\CADsheets\ID366K86-ahs-schedule.dgn

MAINLINE SCHEDULE												
LOCATION	LENGTH	WIDTH	RESURF AREA	HMA SURF REM 1.5"	HMA SURF CSE IL 9.5 MIX C, N70 1.5"	MATL TRANS DEVICE TON	BIT MATL (TACK COAT) POUND	MIX CRACKS JTS & FLANGEWAYS TON	LONG JOINT SEAL FOOT	TEMP RAMP SQ YD	AGG WEDGE SHLD TY B TON	SHOULDER RUMBLE STRIPS, 8" FT
STATION	FOOT	FOOT	SQ FT	SQ YD	TON	TON	POUND	TON	FOOT	SQ YD	TON	FT
URBAN												
STA 1274+63 TO STA 1274+50	13	30	390	43	4	4	29		13	17		
STA 1274+50 TO STA 1274+20	30						RAILROAD OMISSION					
STA 1274+20 TO STA 1273+30	90	30	2700	300	25	25	203	0.1	90	17		
STA 1273+30 TO STA 1272+76	54	37	1998	222	19	19	150	0.1	54			
STA 1272+76 TO STA 1262+73	1003	43	43129	4792	403	403	3235	1.4	1003			
STA 1262+73 TO STA 1252+70	1003	37	37111	4123	346	346	2783	1.2	1003			
URBAN TOTAL				9480	797	797	6400	2.8	2163	34		
RURAL												
STA 1252+70 TO STA 1248+42	428	30	12840	1427	120	120	963	0.4	428		16	856
STA 1248+42 TO STA 1240+15	827	37	30599	3400	286	286	2295	1	827		31	1654
STA 1240+15 TO STA 952+90	28725	30	861750	95750	8043	8043	64631	28.7	28725		1086	57450
STA 952+90 TO STA 950+51	239	36	8604	956	80	80	645	0.3	239	20	9	478
STA 950+51 TO STA 947+99	252						BRIDGE OMISSION - SN 053-0500					
STA 947+99 TO STA 944+90	309	36	11124	1236	104	104	834	0.4	309	20		618
STA 944+90 TO STA 863+40	8150	30	244500	27167	2282	2282	18338	8.2	8150		309	16300
STA 863+40 TO STA 810+50	5290	30	158700	17633	1481	1481	11903	5.3	5290		201	10580
STA 810+50 TO STA 805+91	459	30	13770	1530	129	129	1033	0.5	459	17	17	918
STA 805+91 TO STA 803+65	226						BRIDGE OMISSION - SN 053-0166					
STA 803+65 TO STA 767+00	3665	30	109950	12217	1026	1026	8246	3.7	3665	17	139	7330
RURAL TOTAL				161316	13551	13551	108888	48.5	48092	74	1808	96184
TOTAL					170796	14348	14348	115288	51.3	50255	108	96184



DELINEATOR PANEL SCHEDULE				
STRUCTURE	SIDE	LENGTH	LOCATION	LINEAR DELINEATOR PANELS 4 INCH
		FT		EACH
RURAL				
SN 053-0179 (STA 949+25)	LT	525	0.6 MILES SOUTH OF 1500N RD	8
SN 053-0179 (STA 949+25)	RT	625	0.6 MILES SOUTH OF 1500N RD	9
DITCH	LT	2450	0.25 MILES SOUTH OF 1700 N RD	32
DITCH	RT	600	0.25 MILES SOUTH OF 1700 N RD	9
SN 053-0166 (STA 804+65)	LT	462.5	0.1 MILE NORHT OF 1700N RD	7
SN 053-0166 (STA 804+65)	RT	487.5	0.1 MILE NORHT OF 1700N RD	7
TOTAL				65

LINEAR DELINEATOR PANELS, 4" TO BE ADDED TO EXISTING GUARDRAILS

ADA SCHEDULE							
DESCRIPTION		PORTLAND CEMENT CONCRETE SIDEWALK 4"	SIDEWALK REMOVAL	PAVEMENT REMOVAL	DETECTABLE WARNINGS	CCC&G TYPE B- 6.24	CC&G REM
	CORNER	SQ FT	SQ FT	SQ YD	SQ FT	FT	FT
URBAN							
KRACK ST	NE	265	122	29	20	36	61
KRACK ST	SE	20	20		10		
KRACK ST	SW	17	17		12		
KRACK ST	NW	96	96		8	25	25
JOHN ST	NE	61	61		19		
JOHN ST	SE	87	87		17		
JOHN ST	SW	54	54		16		
JOHN ST	NW	58	58		16		
WATSON ST	NE	54	54		17	10	10
WATSON ST	SE	60	60		18		
WATSON ST	SW	49	49		10	14	14
WATSON ST	NW	52	52		19	15	15
MARTIN ST	NE	93	93		16	29	29
MARTIN ST	SE	28	28		9		
MARTIN ST	SW	95	95		14	11	11
MARTIN ST	NW	112	112		16		
JAMES ST	NE	75	75		16		
JAMES ST	SE	100	100		16		
JAMES ST	SW	74	74		16		
JAMES ST	NW	91	91		16		
NORTH ST	NE	70	70		8		
NORTH ST	SE	33	33		8		
NORTH ST	SW	29	29		8		
NORTH ST	NW	28	28		10	10	10
TOTALS		1701	1558	29	335	150	175



REVISED 5-19-2021

	USER NAME = carminsa	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 103.1920 ' / in.	DRAWN -	REVISED -						326	(123,123X)R3-4&(124)RS-6,SW	LIVINGSTON	27	13
	PLOT DATE = 5/19/2021	CHECKED -	REVISED -		SCALE: SHEET OF SHEETS STA. TO STA.				CONTRACT NO. 66K86				
		DATE -	REVISED -						ILLINOIS FED. AID PROJECT				



REV. 5/24/21

MODEL: Default
FILE NAME: P:\Waterroom.dot\Illinois.gov\FW\DOT\Documents\UDOT_Offices\District_3\Projects\ID366K86\CADD\data\CAD\sheet\ID366K86-sh1-schedule.dgn

 REVISED 5-19-2021

	USER NAME = carminsa	DESIGNED - _____	REVISED - _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEET	SHEET NO.
	PLOT SCALE = 102.7006 ' / in.	DRAWN - _____	REVISED - _____					326	(123,123X)R3-4&(124)RS-6,SW	LIVINGSTON	27	14
	PLOT DATE = 5/19/2021	CHECKED - _____	REVISED - _____		SCALE: _____ SHEET ____ OF ____ SHEETS STA. _____ TO STA. _____			CONTRACT NO. 66K86				
		DATE - _____	REVISED - _____					ILLINOIS FED. AID PROJECT				

 REV. 5/24/21

SIDE ROAD SCHEDULE										
LOCATION			LENGTH	WIDTH	RESURF AREA	HMA SURF REMOVAL VARIABLE DEPTH	BITUMINOUS MATERIAL (TACK COAT)	INCIDENTAL HMA SURFACING	TEMP RAMP	FURNISHED EXCAVATION
ROAD NAME	SIDE	STATION	FT	FT	SQ FT	SQ YD	POUND	TON	SQ YD	CU YD
URBAN										
W KRACK ST	RT	1273+08	20	55	1100	122	55	14	31	0.8
W KRACK ST	LT	1273+08	20	55	1100	122	55	14	31	0.8
ALLEY	RT	1271+40	20	15	300	33	15	4	8	0.8
ALLEY	LT	1271+40	20	15	300	33	15	4	8	0.8
E JOHN STREET	LT	1269+68	20	30	600	67	30	8	17	0.8
E JOHN STREET	RT	1269+68	20	30	600	67	30	8	17	0.8
ALLEY	LT	1267+94	20	15	300	33	15	4	8	0.8
ALLEY	RT	1267+94	20	15	300	33	15	4	8	0.8
E WATSTON STREET	LT	1266+21	20	45	900	100	45	11	25	0.8
E WATSTON STREET	RT	1266+21	20	45	900	100	45	11	25	0.8
ALLEY	RI	1264+50	20	10	200	22	10	2	6	0.8
E MARTIN STREET	LT	1262+74	20	49	980	109	49	12	27	0.8
E MARTIN STREET	RT	1262+74	20	49	980	109	49	12	27	0.8
E JAMES STREET	LT	1259+27	20	35	690	77	35	9	19	0.8
E JAMES STREET	RT	1259+27	20	35	690	77	35	9	19	0.8
ALLEY	LT	1257+50	20	10	200	22	10	2	6	0.8
ALLEY	RT	1257+50	20	12	240	27	12	3	7	0.8
E NORTH STREET	LT	1255+80	20	43	860	96	43	11	24	0.8
E NORTH STREET	RT	1255+80	20	43	860	96	43	11	24	0.8
ALLEY	RT	1254+00	20	16	320	36	16	4	9	0.8
URBAN SUBTOTAL						1381	622	157	346	20
RURAL										
E BULLARD STREET	LT	1252+29	20	40	800	89	40	10	22	0.8
E BULLARD STREET	RT	1252+29	20	40	800	89	40	10	22	0.8
ALLEY	LT	1247+70	20	40	800	89	40	10	22	0.8
STEWART STREET	RT	1243+06	20	57	1140	127	57	14	32	0.8
STEWART STREET	LT	1243+06	20	57	1140	127	57	14	32	0.8
W VAUGHAN STREET	RT	1239+55	20	38	760	84	38	9	21	0.8
W VAUGHAN STREET	LT	1239+55	20	38	760	84	38	9	21	0.8
E 900 N ROAD	RT	1235+18	30	57	1710	190	86	21	32	1.3
E 900 N ROAD	LT	1235+18	30	57	1710	190	86	21	32	1.3
E 1000 N ROAD	RT	1182+26	30	53	1590	177	80	20	29	1.3
E 1000 N ROAD	LT	1182+26	30	53	1590	177	80	20	29	1.3
E 1100 N ROAD	LT	1129+35	30	47	1410	157	71	18	26	1.3
E 1100 N ROAD	RT	1129+35	30	47	1410	157	71	18	26	1.3
E 1200 N ROAD	LT	1076+42	30	57	1710	190	86	21	32	1.3
E 1200 N ROAD	RT	1076+42	30	57	1710	190	86	21	32	1.3
E 1300 N ROAD	LT	1023+57	30	53	1590	177	80	20	29	1.3
E 1300 N ROAD	RT	1023+57	30	53	1590	177	80	20	29	1.3
E 1400 N ROAD	LT	969+95	30	44	1320	147	66	16	24	1.3
E 1400 N ROAD	RT	969+95	30	44	1320	147	66	16	24	1.3
E 1500 N ROAD	RT	916+39	30	48	1440	160	72	18	27	1.3
E 1500 N ROAD	LT	916+39	30	48	1440	160	72	18	27	1.3
E 1600 N ROAD	RT	863+41	53.5	46	2461	273	123	31	26	2.5
E 1600 N ROAD	LT	863+41	53.5	46	2461	273	123	31	26	2.5
E 1700 N ROAD	RT	810+49	52.5	51	2678	298	134	33	28	2.4
E 1700 N ROAD	LT	810+49	52.5	51	2678	298	134	33	28	2.4
RURAL SUBTOTAL						4227	1906	472	678	35
TOTAL						5608	2528	629	1024	55



MODEL: Default
FILE NAME: P:\M\Mainroom.dwg
PROJECT: D:\Projects\1366486\CADData\CA\Sheet\1366486-ht-schedule.dgn



PAVEMENT MARKING SCHEDULE																					
LOCATION	COMMENT	LENGTH	PAINT (2 APPLICATIONS)			THERMOPLASTIC PAVEMENT MARKING								GROOVING FOR	GROOVING FOR	GROOVING FOR	RAISED	RAISED	PREFORMED	GROOVING	
			4" LINE		6" LINE	4" LINE		6" LINE		8" LINE	12" LINE		LETTERS	RECESSED PM	RECESSED PM	RECESSED PM	REF	REF	PLASTIC PM	GROOVING	
			WHITE	YELLOW	YELLOW	WHITE	YELLOW	WHITE	YELLOW	WHITE	WHITE	YELLOW	& SYMBOLS	5"	7"	9"	PM	PM REM	TYPE B - LINE 24"	FOR RECESSED	
STATION		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	EACH	EACH	FOOT	FOOT	
IL 47																					
URBAN																					
STA 1274+63 TO STA 1262+50		1213				552	612	678	303		216		61.2	1164	981		15	15	39	39	
STA 1262+50 TO STA 1252+70		980							245						245		12	12			
URBAN SUBTOTAL		2193				1164		1226			216		61	1164	1226		27	27	39	39	
RURAL																					
STA 1252+70 TO STA 1252+00		70					70		18					70	18		1	1			
STA 1252+00 TO STA 1248+50		350				700	350		88					1050	88		4	4			
STA 1248+50 TO STA 1242+75		575				1150			1732	260		77		1150	1732	260	7	7			
STA 1242+75 TO STA 1239+50		325				650	1136					93		1786			4	4			
STA 1239+50 TO STA 1235+00		450				900	450		113					1350	113		6	6			
STA 1235+00 TO STA 1207+10		2790	11160		1396												35	35			
STA 1207+10 TO STA 1180+62	no pass 1 way	2648	10592	5296	1324												33	33			
STA 1180+62 TO STA 1167+00		1362	5448		682												17	17			
STA 1167+00 TO STA 1158+75	no pass 1 way	825	3300	1650	412												10	10			
STA 1158+75 TO STA 1156+84		191	764		96												2	2			
STA 1156+84 TO STA 1149+32	no pass 1 way	752	3008	1504	376												9	9			
STA 1149+32 TO STA 1143+68		564	2256		282												7	7			
STA 1143+68 TO STA 1136+50	no pass 1 way	718	2872	1436	360												9	9			
STA 1136+50 TO STA 1134+50		200	800		100												3	3			
STA 1134+50 TO STA 1127+00	no pass 1 way	750	3000	1500	376												9	9			
STA 1127+00 TO STA 1121+30		570	2280		286												7	7			
STA 1121+30 TO STA 1111+53	no pass 1 way	977	3908	1954	488												12	12			
STA 1111+53 TO STA 1044+70		6683	26732		3342												84	84			
STA 1044+70 TO STA 1037+00	no pass 1 way	770	3080	1540	386												10	10			
STA 1037+00 TO STA 1034+37		263	1052		132												3	3			
STA 1034+37 TO STA 1027+65	no pass 1 way	672	2688	1344	336												8	8			
STA 1027+65 TO STA 919+15		10850	43400		5426												136	136			
STA 919+15 TO STA 911+80	no pass 1 way	735	2940	1470	368												9	9			
STA 911+80 TO STA 887+30		2450	9800		1226												31	31			
STA 887+30 TO STA 862+00	no pass 1 way	2530	10120	5060	1266												32	32			
STA 862+00 TO STA 775+20		8680	34720		4340												109	109			
STA 775+20 TO STA 768+00	no pass 1 way	720	2880	1440	360												9	9			
STA 768+00 TO STA 767+72		28	112	258																	
STA 767+72 TO STA 758+00		972	3888	6840				600					46.8		600		12	12			
RURAL SUBTOTAL		49470	222092	23360		5406	2551	260	170		47		5406	2551	260		618	618			
TOTAL		51663	222092	23360		6570	3777	260	386		108		6570	3777	260		645	645	39	39	



SHORT TERM PAVEMENT MARKING SCHEDULE			
LOCATION	LENGTH	SHORT TERM PM	SHORT TERM PM REM
STATION	FOOT	FOOT	SQ FT
URBAN			
STA 1274+63 TO STA 1262+50	1213	170	57
STA 1262+50 TO STA 1252+70	980	137	46
URBAN SUBTOTAL	2193	307	103
RURAL			
STA 1252+70 TO STA 1252+00	70	10	3
STA 1252+00 TO STA 1248+50	350	49	16
STA 1248+50 TO STA 1242+75	575	81	27
STA 1242+75 TO STA 1239+50	325	46	15
STA 1239+50 TO STA 1235+00	450	63	21
STA 1235+00 TO STA 1207+10	2790	391	130
STA 1207+10 TO STA 1180+62	2648	371	124
STA 1180+62 TO STA 1167+00	1362	190	63
STA 1167+00 TO STA 1158+75	825	116	39
STA 1158+75 TO STA 1156+84	191	27	9
STA 1156+84 TO STA 1149+32	752	105	35

SHORT TERM PAVEMENT MARKING SCHEDULE			
LOCATION	LENGTH	SHORT TERM PM	SHORT TERM PM REM
STATION	FOOT	FOOT	SQ FT
STA 1149+32 TO STA 1143+68	564	79	26
STA 1143+68 TO STA 1136+50	718	101	34
STA 1136+50 TO STA 1134+50	200	28	9
STA 1134+50 TO STA 1127+00	750	105	35
STA 1127+00 TO STA 1121+30	570	80	27
STA 1121+30 TO STA 1111+53	977	137	46
STA 1111+53 TO STA 1044+70	6683	935	312
STA 1044+70 TO STA 1037+00	770	108	36
STA 1037+00 TO STA 1034+37	263	37	12
STA 1034+37 TO STA 1027+65	672	94	31
STA 1027+65 TO STA 919+15	10850	1519	506
STA 919+15 TO STA 911+80	735	103	34
STA 911+80 TO STA 887+30	2450	343	114
STA 887+30 TO STA 862+00	2530	354	118
STA 862+00 TO STA 775+20	8680	1215	405
STA 775+20 TO STA 768+00	720	101	34
STA 768+00 TO STA 767+72	28	4	1
STA 767+72 TO STA 758+00	972	136	45
RURAL SUBTOTAL	6928	2307	
TOTAL	7908	2614	103



REVISED 5-19-2021

USER NAME = carminsa	DESIGNED -	REVISED -
PLOT SCALE = 102.7006 ' / in.	DRAWN -	REVISED -
PLOT DATE = 5/19/2021	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: _____ SHEET ____ OF ____ SHEETS STA. _____ TO STA. _____

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(123,123X)R3-4&(124)RS-6,SW	LIVINGSTON	27	16
CONTRACT NO. 66K86				
ILLINOIS FED. AID PROJECT				

MODEL: Default
FILE NAME: P:\Mainroom.dwg
PROJECT: 3\Projects\0366\06\CADD\data\CA\Drawings\0366\06\ht-schedule.dgn

DRAINAGE SCHEDULE								
STATION	TYPE/SIZE	STRUCTURE NUMBER	LOCATION DESCRIPTION	DELINEATORS	REATTACH END SEC	CONNECTING END SEC	STONE RR, CLASS A4	POROUS GRANULAR EMBANKMENT
				EACH	EACH	EACH	SQ YD	CU YD
RURAL								
1083+05	42" RCP	2145	EAST SIDE OF CULVERT	2	1			- - - - -
863+00	24" RCP	2148	DOWNSTREAM	2	1	1	40	70
TOTAL				4	2	1	40	70



MAINTENANCE SCHEDULE							
STATION	TYPE/SIZE	STRUCTURE NUMBER	LOCATION DESCRIPTION	DELINEATORS	STONE RR, CLASS A4	FURNISHED EXCAVATION	SEEDING CLASS 2
				EACH	SQ YD	CU YD	ACRE
RURAL							
1115+97	9X4 BOX CULV	053-2546	DOWNSTREAM FACE	2	16		
844+00	3X2 BOX CULV	2149	WEST END SEC	2	9		
836+98	8X4 BOX CULV	053-2590	RIPRAP AT OUTLET BELOW THE STRUCTURE	2	3		
828+30	3X2 BOX CULV	2150	WEST END SEC	2	9		
804+65	3 SPAN BRIDGE	053-0166	EAST EDGE OF BOTH APPROACH SLABS	2		20	0.25
TOTAL				10	37	20	0.25

FURNISHED EXCAVATION SHALL BE PLACED ALONG THE EAST EDGE OF BOTH APPROACH SLABS OF SN 053-0166



DITCH CLEANING SCHEDULE							
LOCATION			SIDE	LENGTH	FLOW DIRECTION	GRADING & SHAPING	
				FOOT		DITCH	FOOT
RURAL							
STA 1238+50	TO STA 1240+30	EAST	180	SOUTH	180		
STA 1235+50	TO STA 1238+00	EAST	250	SOUTH	250		
STA 1172+00	TO STA 1174+50	EAST	250	NORTH	250		
STA 1089+50	TO STA 1091+00	EAST	150	NORTH	150		
STA 1082+00	TO STA 1083+00	EAST	100	NORTH	100		
STA 1076+80	TO STA 1078+00	EAST	120	NORTH	120		
STA 1070+00	TO STA 1071+00	WEST	100	SOUTH	100		
STA 1050+50	TO STA 1051+50	EAST	100	NORTH	100		
STA 1044+00	TO STA 1045+50	WEST	150	NORTH	150		
STA 1043+00	TO STA 1044+00	WEST	100	SOUTH	100		
STA 1019+50	TO STA 1021+50	WEST	200	NORTH	200		
STA 992+00	TO STA 993+50	WEST	150	NORTH	150		
STA 983+50	TO STA 984+50	WEST	100	NORTH	100		
STA 886+65	TO STA 888+15	WEST	150	NORTH	150		
STA 886+65	TO STA 887+65	EAST	100	NORTH	100		
STA 886+15	TO STA 886+65	WEST	50	SOUTH	50		
STA 862+00	TO STA 863+00	EAST	100	NORTH	100		
STA 758+00	TO STA 758+60	WEST	60	NORTH	60		
TOTAL						2410	

ADJUSTMENT SCHEDULE				
LOCATION	WATERMAIN MANHOLES	WATER VALVES	FIRE HYDRANT	FRAMES AND LIDS
	TO BE ADJUSTED	TO BE ADJUSTED	TO BE ADJUSTED	TO BE ADJUSTED
	EACH	EACH	EACH	EACH
URBAN				
1273+20				1
1272+86		2		
1271+62				1
1271+32				2
1271+27	1		1	
1270+00		1		
1268+00		2		1
1266+28				1
1266+00				
1265+00				1
1264+55				2
1263+20		1		
1261+00				1
1260+00		1		
1259+23				1
1257+55				1
1254+28		1		
TOTAL	1	8	1	12



REVISED 5-19-2021

	USER NAME = carminsa	DESIGNED - _____	REVISED - _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P. RTE. 326	SECTION (123.123X)R3-4&(124)RS-6.SW	CCUNTY LIVINGSTON	TOTAL SHEETS 27	SHEET NO. 17
	PLOT SCALE = 103.3694 ' / in.	CHECKED - _____	REVISED - _____					CONTRACT NO. 66K86				
	PLOT DATE = 5/19/2021	DATE - _____	REVISED - _____		SCALE: _____	SHEET ____ OF ____ SHEETS	STA. _____ TO STA. _____	ILLINOIS FED. AID PROJECT				



REV. 5/24/21