

Note:

The design fill height for this structure is 5 feet. The precast concrete box culvert sections shall conform to the standard designs of ASTM C 1577.

The box culvert end section shall be built in the field and a precast option is not allowed except the cutoff wall may be precast. If the Contractor elects to use a precast cutoff wall, shop drawings and a proposed construction sequence shall be submitted to the Engineer for approval.

Areas of the precast box culvert in contact with cast-in-place concrete shall be sandblasted, cleaned, and wetted prior to placing concrete in the field according to Article 503.09(b).

The ends of the precast box sections adjacent to the end section shall be formed without male and female shapes.

The joints between precast box sections shall be sealed, all voids filled with a mastic joint sealer. In addition, the joints shall be externally sealed on all four sides with a 13 inch wide external sealing band. The seal shall be centered over the joint, secured in place and protected during the backfilling process.

Tilt h2 and h3 bars as required to maintain clearance. Extend precast concrete box culvert reinforcement into

end section. Bend as necessary to provide $1\frac{1}{2}$ " clear cover. See sheets CUL-3 & 4 of 10 for culvert construction sequence. See sheets CUL-7 & 8 of 10 for Section A-A, B-B, C-C, C'-C', D-D, and E-E.

See sheet CUL-5 of 10 for additional wing wall details. Bars indicated thus 4 x 2-#5 etc. indicates 4 lines of bars with 2 lengths per line.



TYPICAL INTERMEDIATE HEADWALL

Intermediate headwalls to be precast

					C	UL-07
F.A.P. RTE	SEC	ΓION		COUNTY	TOTAL SHEETS	SHEET NO.
344	2020-196-T			DUPAGE	122	62
NO. 022-8300 344 2020-196-1				CONTRACT NO. 62M69		
		ILLINOIS	FED. AID PROJECT			
			344 2020-196-T	344 2020-196-T	344 2020-196-T DUPAGE CONTRACT	F.A.P. RTE. SECTION COUNTY TOTAL SHEETS 344 2020-196-T DUPAGE 122 CONTRACT NO. 62