



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 1, 2021

SUBJECT FAI Route 55 (I-55)
Project NHPP_R5LY(895)
Section 22-36HB-1
DuPage County
Contract No. 62G39
Item No. 206, June 11, 2021 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices
2. Revised page ii of the Table of Contents to the Special Provisions
3. Revised page 137 of the Special Provisions
4. Revised sheets 5, 8, 10, 11, 13, 14, 16-20, 22-24, 70-77, 90, 95 109, 114, 118-120, 138, 140-143, 160, 164-167, 184, 197-205 & 207 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

UNDERPASS LUMINAIRE, LED (D1).....	102
UNIT DUCT (D1).....	115
WIRE AND CABLE (D1)	116
LUMINAIRE SAFETY CABLE ASSEMBLY (D1)	117
KEEPING THE EXPRESSWAY OPEN TO TRAFFIC (D1).....	118
FAILURE TO OPEN TRAFFIC LANES TO TRAFFIC (D1)	121
TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS) (D1).....	121
TRAFFIC CONTROL SURVEILLANCE (EXPRESSWAYS) (D1)	126
TEMPORARY INFORMATION SIGNING (D1).....	127
TRAFFIC CONTROL FOR WORK ZONE AREAS (D1)	128
SPEED DISPLAY TRAILER (D1)	129
SIGN SHOP DRAWING SUBMITTAL (D1)	130
TRAFFIC CONTROL AND PROTECTION (SPECIAL)	130
PROGRESS SCHEDULE	131
WORKING RESTRICTIONS.....	132
CONTRACTOR ACCESS.....	133
CONTRACTOR STAGING AREA.....	134
APPROACH SLAB REMOVAL.....	134
CHAIN LINK FENCE, 42" ATTACHED TO STRUCTURE (SPECIAL).....	135
CHAIN LINK FENCE REMOVAL.....	136
CLEANING EXISTING DRAINAGE STRUCTURES	136
GRADING AND SHAPING OF FORESLOPES AND INFIELDS.....	137
HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	138
INLETS TO BE ADJUSTED.....	138
MEDIAN SURFACE REMOVAL	139
PAVED SHOULDER REMOVAL (SPECIAL)	139
PILE EXTRACTION	140
ABANDON AND FILL EXISTING STORM SEWER	141
PROPOSED STORM SEWER CONNECTION TO EXISTING MANHOLE	142
RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	142
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC).....	143
SHOULDER RUMBLE STRIP REMOVAL.....	146
STABILIZED CONSTRUCTION ENTRANCE	146
STORM SEWERS TO BE CLEANED	147
TEMPORARY PAVEMENT REMOVAL.....	149
TOPSOIL EXCAVATION AND PLACEMENT	149

GRADING AND SHAPING OF FORESLOPES AND INFIELDS

This work shall consist of grading and shaping existing ditches, slopes and infiel embankments and slopes after the removal of Temporary Pavement as directed by the Engineer, and in accordance with Sections 202, 204 and 205 of the Standard Specifications.

The applicable areas match the footprint of the ground impacted by the construction and maintenance of the temporary ramp widening and intersection approaches. The limits of this work as shown on the plans is approximate. Actual grading and shaping limits shall be determined by the Engineer. In locations where temporary pavement is removed, grading and shaping shall reinstate existing ground contours. It is the responsibility of the contractor to verify existing grades, contours, and flow drainage flow patterns prior to beginning construction operations for use in restoring these conditions following completion of the project improvement.

Immediately after grading and shaping is completed, the permanent landscaping and necessary erosion control measures specified and scheduled in the plans will be put in place. Failure to place specified erosion control will result in additional reshaping of the ditches and slopes by the Contractor at his/her expense.

Grading and Shaping Foreslopes and Infields will be not be measured for payment. Quantities of Earth Excavation, Furnished Embankment, and Landscaping measures are included in the contract and shown in the plans.

Revised 5/27/2021