

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN () WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL (2) SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

| FILE NAME = | USER NAME = gaglianobt | DESIGNED - | REVISED - R. MIRS 09-15-97 | | ARTERIAL ROAD | F.A.P. SECTION | COUNTY TOTAL SHEET |
|---|-----------------------------|------------|--------------------------------|------------------------------|--|----------------|--------------------|
| c:\pw_work\pwidot\gaglianobt\dms92488\D | stStd.dgn | DRAWN - | REVISED - R. MIRS 12-11-97 | STATE OF ILLINOIS | | 350 3321-S-RS | COOK 2 7 24 |
| | PLOT SCALE = 50.0000 '/ IN. | CHECKED - | REVISED -T. RAMMACHER 02-02-99 | DEPARTMENT OF TRANSPORTATION | INFORMATION SIGN | TC-22 | CONTRACT NO. 60B54 |
| | PLOT DATE = 2/6/2009 | DATE - | REVISED - C. JUCIUS 01-31-07 | | SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA. | | ID PROJECT |