

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE										
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	90% FED. 10% STATE		TRAFFIC SIGNAL 4031-IF 90% FED. 10% STATE					CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	90% FED. 10% STATE		TRAFFIC SIGNAL 4031-IF 90% FED. 10% STATE					
				1000-2A	1000-2A VILLAGE 100%										1000-2A	1000-2A VILLAGE 100%						
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1	1						48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	80	80								
20200100	EARTH EXCAVATION	CU YD	1620	1620						48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SO YD	210	210								
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1595	1595						54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2	2								
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	420	420						550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	15	15								
28000400	PERIMETER EROSION BARRIER	FOOT	2,172	2,172						550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	28	28								
21101625	TOPSOIL FURNISH AND PLACE, 6"	SO YD	4677	4677						55039700	STORM SEWERS TO BE CLEANED	FOOT	50	50								
25000210	SEEDING, CLASS 2A	ACRE	0.55	0.55						60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	2	2								
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	75	75						60107600	PIPE UNDERDRAINS 4"	FOOT	120	120								
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	75	75						60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	1	1								
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	75	75						60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	1	1								
25100630	EROSION CONTROL BLANKET	SO YD	2677	2677						60500060	REMOVING INLETS	EACH	1	1								
25200110	SODDING, SALT TOLERANT	SO YD	2000	2000						60603300	GUTTER OUTLET	EACH	7	7								
28000300	TEMPORARY DITCH CHECKS	EACH	15	15						67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9								
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SO YD	1370	1370						67100100	MOBILIZATION	L SUM	1	1								
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SO YD	1370	1370						70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1								
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5	5						70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1								
40600300	AGGREGATE (PRIME COAT)	TON	22	22						70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1								
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	2	2						70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1								
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	180	135	45					70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10								
40600895	CONSTRUCTING TEST STRIP	EACH	1	1						70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1				1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	110	110						70300100	SHORT-TERM PAVEMENT MARKING	FOOT	500	500								
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	90		90					70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	430	430								
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	990	990						70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3920	3920								
42001300	PROTECTIVE COAT	SO YD	1935	1935						70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1840	1840								
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	925	885			40			70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	90	90								
42400800	DETECTABLE WARNINGS	SO FT	80	80						70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	180	180								
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SO YD	8700	8700						72000100	SIGN PANEL - TYPE 1	SO FT	18				18					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	1000		1000					72000200	SIGN PANEL - TYPE 2	SO FT	50				50					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	760	760						78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	321	321								
44000600	SIDEWALK REMOVAL	SO FT	1450	1450						78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3550	3550								
44004250	PAVED SHOULDER REMOVAL	SO YD	1250	1250						78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1500	1500								
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1750	1750																		
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SO YD	160	160																		