

NOTES:

- 1. THE WIDTH OF THE FULL DEPTH PATCH OVER A TRENCH SHALL BE 12 (300) WIDER ON EACH SIDE OF THE TRENCH.
- 2. FOR METHOD OF MEASUREMENT AND BASIS OF PAYMENT, SEE RECURRING SPECIAL PROVISION "PATCHING WITH HOT-MIX ASPHALT OVERLAY REMOVAL".

SEQUENCE OF CONSTRUCTION

- 1. REMOVE THE EXISTING HMA MATERIAL OVER THE AREA TO BE PATCHED.
- 2. REMOVE AND REPLACE FULL DEPTH PATCHES
- 3. REPLACE HMA MATERIAL OVER THE AREA TO BE PATCHED.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FILE NAME =	USER NAME = tthornton	DESIGNED -	REVISED -		NEW STEARNS ROAD - STAGE 2	F.A.P SECTION	COUNTY TOTAL SHEET SHEETS NO.
::\dgn\c:v:l\sheet\sd001.dgn		DRAWN -	REVISED -	KANE COUNTY	PAVEMENT PATCHING FOR BITUMINOUS SURFACED PAVEMENT	361 06-00214-10-BR	KANE 219 82
	PLOT SCALE = 1:10	CHECKED -	REVISED -	DIVISION OF TRANSPORTATION	PAYLINEIAL LYLCHING LOU DILONINGOO SOULAGED LYCHICA	BD-22	CONTRACT NO. 63073
	PLOT DATE = 3/29/2009	DATE - 3/27/09	REVISED		SCALE: SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FEE	D. AID PROJECT