

SCHEDULE OF QUANTITIES

PAY ITEM	UNIT	TOTAL	AYER STREET	MARENGO ROAD	MCKINLEY STREET
BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2566	1290	496	780
AGGREGATE (PRIME COAT)	TON	33	16.5	6.5	10
LEVELING BINDER MACHINE METHOD, N50	TON	1154	580	223	351
HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	340	143.5	51.2	145.3
HOT-MIX ASPHALT SURFACE COURSE, MIX "C" N50	TON	1385	696	268	421
HOT-MIX SURFACE REMOVAL 1-1/2"	SQ YD	16026	8060	3096	4870
CLASS D PATCHES, TYPE 1, 6 INCH	SQ YD	2200	1120	613	467
AGGREGATE SHOULDER, TYPE B	TON	34.19	17.18	17.01	0
FRAMES AND LIDS TO BE ADJUSTED	EACH	32	16	1	15
SHORT-TERM PAVEMENT MARKING	FOOT	60	60	0	0
WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	20	20	0	0
THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	41.6	41.6	0	0
THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3029	3029	0	0
THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	654	498	0	156
THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	15	0	0	15
PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	31.2	31.2	0	0
PAINT PAVEMENT MARKING - LINE 4"	FOOT	1085	1085	0	0
PAINT PAVEMENT MARKING - LINE 6"	FOOT	70	70	0	0
PAVEMENT MARKING REMOVAL	SQ FT	176.75	176.75	0	0
DRIVEWAY PAVEMENT REMOVAL	SQ YD	554	340	214	0
DRIVEWAY PAVEMENT	SQ YD	844	577	267	0

AGGREGATE SHOULDER, TYPE B SCHEDULE

AYER STREET	MARENGO ROAD	MCKINLEY STREET
100+68 TO 101+35 LT 1.29 TONS	200+26 TO 200+99 LT 0.80 TONS	NONE
100+72 TO 100+82 RT 0.09 TONS	200+26 TO 201+65 RT 1.76 TONS	
101+61 TO 102+90 LT 1.63 TONS	201+41 TO 202+45 LT 1.35 TONS	
101+14 TO 102+89 RT 2.62 TONS	201+87 TO 202+74 RT 1.74 TONS	
103+52 TO 103+85 RT 0.52 TONS	202+67 TO 204+13 LT 1.85 TONS	
104+04 TO 104+49 RT 0.65 TONS	203+22 TO 204+24 RT 1.67 TONS	
104+70 TO 106+14 RT 2.33 TONS	204+43 TO 205+41 RT 1.61 TONS	
106+78 TO 107+49 RT 1.37 TONS	204+45 TO 205+42 LT 1.05 TONS	
107+79 TO 108+77 RT 1.61 TONS	205+50 TO 205+88 LT 0.49 TONS	
109+05 TO 111+55 RT 5.07 TONS	206+14 TO 206+68 LT 1.19 TONS	
	206+92 TO 208+50 LT 3.50 TONS	
	17.01 TONS	

DRIVEWAY SURFACE SCHEDULE

AYER STREET	MARENGO ROAD	MCKINLEY STREET
101+00 RT 19 SQ YD	203+00 RT 70 SQ YD	NONE
101+50 LT 17 SQ YD	204+35 LT 64 SQ YD	
103+40 RT 101 SQ YD	204+40 RT 28 SQ YD	
104+00 RT 73 SQ YD	205+45 LT 5 SQ YD	
104+55 RT 13 SQ YD	206+00 LT 52 SQ YD	
107+50 RT 96 SQ YD	206+75 LT 48 SQ YD	
107+75 LT 47 SQ YD	267 SQ YD	
108+50 LT 56 SQ YD		
108+80 RT 85 SQ YD		
111+75 LT 9 SQ YD		
113+85 RT 13 SQ YD		
114+35 RT 9 SQ YD		
114+50 LT 22 SQ YD		
115+00 RT 13 SQ YD		
115+20 LT 4 SQ YD		
577 SQ YD		

HARVARD 2009 LAPP  
 HARV-080606  
 080606-sch.dgn