

SCHEDULE OF QUANTITIES

PAY ITEM #	ITEM	UNIT	TOTAL QUANTITY	STA. 10+06 TO STA. 17+50	STA. 17+50 TO STA. 27+00	STA. 27+00 TO STA. 33+00
20100210	TREE REMOVAL (OVER 15 UNITS DIA)	UNITS	146	0	48	98
20200500	EARTH EXCAVATION (WIDENING)	CY	1308	432	536	340
20700220	POROUS GRANULAR EMBANKMENT	CY	100	100	0	0
20800150	TRENCH BACKFILL	CY	640	280	280	80
21101615	TOPSOIL FURNISH AND PLACE, 4"	SY	5150	1730	1820	1600
25200110	SODDING, SALT TOLERANT	SY	5150	1730	1820	1600
25200200	SUPPLEMENTAL WATERING	UNIT	50	17	21	12
28000400	PERIMETER EROSION BARRIER	FOOT	3794	1264	1410	1120
28000510	INLET FILTERS	EA	35	14	16	5
35102000	AGGREGATE BASE COURSE TYPE B - 8"	SY	180	180	0	0
35600708	HOT-MIX ASPHALT BASE COURSE WIDENING - 8"	SY	2940	971	1205	764
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	720	238	295	187
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	120	40	49	31
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	0	0
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19, N50	TON	1114	368	457	289
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX C, N50	TON	780	258	320	202
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SF	6650	2195	2726	1729
42400800	DETECTABLE WARNINGS	SF	500	165	205	130
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SY	6680	2204	2740	1736
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	4610	1522	1890	1198
44000600	SIDEWALK REMOVAL	SF	6650	2194	2726	1730
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	990	400	490	100
55019800	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 21"	FOOT	25	0	25	0
55020000	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 27"	FOOT	20	20	0	0
55100300	STORM SEWER REMOVAL, 8"	FOOT	750	330	320	100
56400500	FIRE HYDRANT TO BE REMOVED	EA	2	2	0	0
56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EA	2	2	0	0
60218400	MANHOLES, TYPE A, 4' DIAMETER TYPE 1 FRAME, CLOSED LID	EA	3	1	1	1
60221100	MANHOLES, TYPE A, 5' DIAMETER TYPE 1 FRAME, CLOSED LID	EA	1	0	1	0
60236900	INLETS, TYPE A, TYPE 12 FRAME AND GRATE	EA	35	14	16	5
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EA	22	9	9	4
60500060	REMOVING CATCHBASINS	EA	35	14	16	5
60603800	COMBINATION CONCRETE CURB AND GUTTER TYPE B-6-12	FOOT	4610	1520	1890	1200
67100100	MOBILIZATION	LS	1	1	0	0
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	LS	1	1	0	0
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4080	1348	1672	1060
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	600	198	246	156
X0322924	RETAINING WALL REMOVAL	SF	180	0	180	0
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SY	1380	457	565	358
XX001910	PRECAST BLOCK RETAINING WALL	SF	180	0	180	0
XX003435	PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT	SY	1510	500	620	390
20076600	TRAINEES	HOUR	500	165	205	130

TREE REMOVAL SCHEDULE (UNITS DIA.)		
STATION	DISTANCE FROM CENTER LINE	OVER 15" DIA.
19+94	19' R	48"
31+72	16' L	42"
31+93	14' L	20"
32+65	15' L	36"