

- 1. THE EDWIN HANCOCK ENGINEERING COMPANY SHALL BE NOTIFIED AT LEAST TWO (2) WORKING DAYS PRIOR TO COMMENCEMENT OF CONSTRUCTION AT (708) 865-0300.
- 2. THE VILLAGE OF MELROSE PARK PUBLIC WORKS DEPARTMENT SHALL BE NOTIFIED AT LEAST TWO (2) WORKING DAYS PRIOR TO COMMENCEMENT OF CONSTRUCTION AT (708) 343-4000.
- 3. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE "STANDARD SPECIFICATIONS FOR SEWER AND WATER MAIN CONSTRUCTION IN ILLINOIS" AND THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION".
- 4. THE CONTRACTOR SHALL SAW CUT ALL BUTT JOINTS TO ADJOINING PAVEMENTS NOT MORE THAN 24 HOURS PRIOR TO PLACING SURFACE COURSE.
- 5. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO TAKE PRECAUTIONS SO AS NOT TO DAMAGE PARKWAY'S AND CURB OUTSIDE THE PRESCRIBED LIMITS OF RESTORATION. NO PARKWAY OR CURB RESTORATION IS INCLUDED FOR PAYMENT EXCEPT AS NECESSARY FOR STRUCTURE ADJUSTMENTS AND REPLACEMENT, OR AS DIRECTED BY ENGINEER.
- 6. STOCKPILING OF MATERIALS ON THE PARKWAYS OR CURB WILL NOT BE ALLOWED, INCLUDING EXCAVATED MATERIAL OR TRENCH BACKFILL MATERIAL. THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORING ANY DAMAGE TO THE PARKWAY OR SOD OUTSIDE OF THE PRESCRIBED LIMITS TO THE SATISFACTION OF THE ENGINEER AND THE VILLAGE AT HIS OWN EXPENSE
- 7. THE LOCATIONS FOR PATCHING WORK SHALL BE DETERMINED IN THE FIELD BY THE ENGINEER AND THIS WORK SHALL BE PERFORMED AS DIRECTED BY THE ENGINEER.






MINIMUM OF 2" AND MAXIMUM OF 6" OF PRECAST REINFORCED CONCRETE ADJUSTMENT RINGS



**COMBINATION CONCRETE CURB & GUTTER** TYPE B-6.12 (MODIFIED)





**CAST-IN-PLACE DETECTABLE WARNINGS** 

USER NAME DESIGNED WOP REVISED LEV/MK REVISED CHECKED JCG REVISED

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION** 

COUNTY **DETAILS AND NOTES** 08-00112-00-RS 2733 COOK 19 7 CONTRACT NO. 63173 SHEET NO. OF SHEETS STA.

E.H.E. PROJECT NO. 600-08-23301