

SCHEDULE OF QUANTITIES

PAY ITEM #	DESCRIPTION	UNIT	Comments	PAY ITEM #	DESCRIPTION	UNIT	Comments
20100110	Tree Removal (6 to 15 diameter units)	Unit		25000400	Nitrogen Fertilizer Nutrient	Pound	
	LOCATION				LOCATION		
	787+27.99 LT	6			781+00 - 784+84.4 RT	41.4	
	789+86.21 LT	7			785+50 - 793+00 RT	145.8	
	790+28.38 LT	8			793+50 - 795+81.3 RT	16.2	
	790+41.77 LT	6			781+50 - 795+81.3 LT	206.1	
	793+61.85 RT	8			TOTAL =	409.5	
	793+81.34 RT	6					
	793+92.61 RT	6					
	TOTAL =	47					
20100210	Tree Removal (Over 15 diameter units)	Unit		25000500	Phosphous Fertilizer Nutrient	Pound	
	LOCATION				LOCATION		
	786+43.82 LT	36			781+00 - 784+84.4 RT	41.4	
	786+49.99 LT	42			785+50 - 793+00 RT	145.8	
	786+55.41 LT	34			793+50 - 795+81.3 RT	16.2	
	786+90.32 LT	38			781+50 - 795+81.3 LT	206.1	
	787+15.43 LT	36			TOTAL =	409.5	
	787+21.79 LT	40					
	787+48.59 LT	42					
	787+80.60 LT	45					
	788+04.45 LT	48					
	789+83.11 LT	40					
	789+95.12 LT	48					
	791+35.35 LT	48					
	791+63.23 LT	50					
	TOTAL =	547					
20100500	Tree Removal, Acres	Acre		25000600	Potassium Fertilizer Nutrient	Pound	
	LOCATION				LOCATION		
	786+27.65 - 791+80.60 RT	1.09			781+00 - 784+84.4 RT	41.4	
	TOTAL =	1.09			785+50 - 793+00 RT	145.8	
					793+50 - 795+81.3 RT	16.2	
					781+50 - 795+81.3 LT	206.1	
					TOTAL =	409.5	
20200100	Earth Excavation	Cu. Yd.		25100115	Mulch Method 2	Acre	
	See Earthwork Schedule	12557			LOCATION		
	TOTAL =	12557			781+00 - 784+84.4/785+50 - 795+81.3 RT	2.32	
					781+50 - 795+81.3 LT	2.13	
					TOTAL =	4.45	
20201200	Removal and Disposal of Unsuitable Material	Cu. Yd.		25100900	Turf Reinforcement Mat	Sq. Yd.	
	LOCATION				LOCATION		
	781+00 - 795+81.3	50			781+50 - 784+92 RT	872.44	
	TOTAL =	50			785+42 - 795+80 RT	2981.77	
					781+50 - 795+80 LT	4196.59	
					TOTAL =	8050.8	
21301052	Exploration Trench 52" Depth	Foot		28000300	Temporary Ditch Checks	Each	
	LOCATION				LOCATION		
	786+92.15 RT	50			781+50-783+50 RT	7	33' Centers
	790+12.47 RT	50			783+50-784+50 RT	2	50' Centers
	787+14.6 LT	50			785+50-786+00 RT	4	12.5' Centers
	789+79.32 LT	50			786+00-787+00 RT	5	20' Centers
	TOTAL =	200			787+00-793+00 RT	12	50' Centers
					793+00-794+00 RT	3	25' Centers
					794+00-795+00 RT	3	33' Centers
					795+00-795+50 RT	2	25' Centers
					795+00-795+81.3 RT	1	15' Centers
25000210	Seeding Class 2A	Acre					
	LOCATION						
	781+00 - 784+84.4 RT	0.13			781+50-783+50 LT	5	50' Centers
	785+50 - 793+00 RT	1.00			783+50-784+00 LT	2	25' Centers
	793+50 - 795+81.3 RT	0.09			784+00-785+50 LT	3	50' Centers
	781+50 - 795+81.3 LT	1.10			785+50-787+00 LT	12	12.5' Centers
	TOTAL =	2.32			787+00-789+00 LT	2	100' Centers
					789+00-789+50 LT	2	25' Centers
					789+50-791+00 LT	9	17' Centers
					791+00-792+00 LT	4	25' Centers
					792+00-792+50 LT	4	12.5' Centers
					792+50-793+00 LT	1	50' Centers
					793+00-795+00 LT	6	33' Centers
					795+00-795+50 LT	4	12.5' Centers
					795+50-795+81.3 LT	1	31.3'
	TOTAL =	2.13			TOTAL =	94	
25000310	Seeding Class 4	Acre					
	LOCATION						
	781+00 - 784+84.4 RT	0.33					
	785+50 - 793+00 RT	0.62					
	793+50 - 795+81.3 RT	0.09					
	781+50 - 795+81.3 LT	1.09					
	TOTAL =	2.13					