## **GENERAL NOTES**

All Borrow/Waste/Use sites must be approved by the Department prior to removing any material from the project or initiating any earthmoving activities, including temporary stockpiling outside the limits of construction.

The Contractor shall seed all disturbed areas within the project limits. Seeding Class 4 or 2A shall be used, except in front of properties where the grass will be mowed, then use Seeding, Class 1, Class 2A shall be used on front slopes and ditch bottoms. Class 4 shall be used behind Type A gutter, on all backslopes and areas behind the backslope, and beyond the toe of front slope on fill sections without ditches. This work will be included in the contract unit price per Lump Sum for Mobilization.

Fertilizer shall be applied to all disturbed areas and incorporated into the seedbed prior to seeding or placement of sod at the rate specified in Sections 250 and 252 of the Standard Specifications. This work shall be included in the cost of MOBILIZATION.

Mulch Method II shall be applied over all seeded areas. This shall be included in the cost of the MOBILIZATION.

This structure will retain the same number 043-0027.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123.

## **SUMMARY OF QUANTITIES**

paycode	pay item
0500405	FURNISHING AND ERECTING STRUCTURAL STEEL
7100100	MOBILIZATION
0100450	TRAFFIC CONTROL AND PROTECTION, STANDARD
and the second	
· · · · · · · · · · · · · · · · · · ·	
<u>en en e</u>	

ILE NAME =	USER NAME = linkdj	DESIGNED	REVISED -		Summary of Quantities	F.A.P. SECTION	COUNTY TOTAL SHEET NO.
D:\BR\CADD plans\Jo Daviess County\0430	127\0430027.dgn	DRAWN	REVISED -	STATE OF ILLINOIS	General Notes	308 (103BR-2)M	JoDaviess 4 2
	PLDT SCALE = 50.0000 // IN.	CHECKED	REVISED -	DEPARTMENT OF TRANSPORTATION			CONTRACT NO. 64E92
and the second standing the second states	PLOT DATE = Mon Mor 09 10:39:21 2009	DATE	REVISED -		SCALE: SHEET NO OF SHEETS STA TO STA	ILLINOIS FED. AI	AID PROJECT

5



		SFTY-ZA
	units	quantity
	POUND	24170
	L SUM	1
01201	L SUM	1

	100% STATE SFTY-ZA TOTAL
units	quantity
	and a start of the start of the
POUND	24170
L SUM	1
	1. · · · · · · · · · · · · · · · · · · ·