

# GENERAL NOTES

The Contractor shall seed all disturbed areas within the project limits. Seeding Class 4 or 2A shall be used, except in front of properties where the grass will be mowed, then use Seeding, Class 1. Class 2A shall be used on front slopes and ditch bottoms. Class 4 shall be used behind Type A gutter, on all backslopes and areas behind the backslope, and beyond the toe of front slope on fill sections without ditches. This work will be included in the contract unit price per Lump Sum for Mobilization.

Fertilizer shall be applied to all disturbed areas and incorporated into the seedbed prior to seeding or placement of sod at the rate specified in Sections 250 and 252 of the Standard Specifications. This work shall be included in the cost of MOBILIZATION.

Mulch Method II shall be applied over all seeded areas. This shall be included in the cost of the MOBILIZATION.

These structures will retain the same number 071-0059 & 071-0060.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123.

Work on this contract will be in progress at the same time as work on a contract at the I-39 & I-88 Interchange. Coordination of the contractors will be required to avoid conflicts with traffic control. A gap of less than one mile between lane closures will not be allowed.

# SUMMARY OF QUANTITIES

paycode	description	units	100% STATE
			SFTY-2A
			quantity
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQFT	11.5
X0322194	POLYMER MODIFIED PORTLAND CEMENT MORTAR	SQFT	19.4
X0324126	GALVANIC ANODE	EACH	8
67100100	MOBILIZATION	L SUM	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1