

80% FED.
20% STATE

SUMMARY OF QUANTITIES						
CODE NO.	ITEM	UNIT	URBAN		RURAL	
			TOTAL	I000	SFTY-1B	Y031 -1F
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	7149	7149		
40600300	AGGREGATE (PRIME COAT)	TON	171	171		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	27	27		
40600535	LEVELING BINDER (HAND METHOD), N70	TON	45	45		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	3578	3578		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600990	TEMPORARY RAMP	SQ YD	858	858		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	6489	6489		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	655	655		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	87104	87104		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	10438		10438	
44002805	ISLAND REMOVAL	SQ FT	2377		2377	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	868		868	
44000600	SIDEWALK REMOVAL	SQ FT	10438		10438	
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	14			14
42400800	DETECTABLE WARNINGS	SQ FT	762		762	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	90	90		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	290	290		
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	79	79		
60611600	COMBINATION CONCRETE CURB AND GUTTER, (SPECIAL)	FOOT	868		868	
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	1	1		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1		1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	14385	14385		
70300610	TEMPORARY PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	4297	4297		
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	34760	34760		
70300635	TEMPORARY PAINT PAVEMENT MARKING LINE 6"	FOOT	13253	13253		
70300640	TEMPORARY PAINT PAVEMENT MARKING LINE 8"	FOOT	4700	4700		
70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT	5005	5005		
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	2868	2868		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1582	1582		
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2089	2089		
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	29971	29971		
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	7683	7683		
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	4700	4700		
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	5005	5005		