

SUMMARY OF QUANTITIES

CONSTRUCTION CODE SFTY-2A

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	RURAL 100% STATE SN 050-0170 (NB) PPS# 0-01616-3002
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	600	600
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	1120	1120
44200541	CLASS 1 PATCHES, TYPE II, 9"	SQ YD	50	50
48203033	HOT-MIX ASPHALT SHOULDERS 9"	SQ YD	1120	1120
50102400	CONCRETE REMOVAL	CU YD	28	28
50300225	CONCRETE STRUCTURES	CU YD	6	6
50300255	CONCRETE SUPERSTRUCTURE	CU YD	22	22
50300260	BRIDGE DECK GROOVING	SQ YD	567	567
50300300	PROTECTIVE COAT	SQ YD	600	600
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	5172	5172
50800515	BAR SPLICERS	EACH	50	50
52000110	PREFORMED JOINT STRIP SEAL	FOOT	85	85
59000210	EPOXY CRACK SEALING	FOOT	15	15
67100100	MOBILIZATION	L SUM	0.5	0.5
70101605	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	EACH	1	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	400	400
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	375	375
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1410	1410
78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	260	260
78300100	PAVEMENT MARKING REMOVAL	SQ FT	595	595
X0321468	PLUG EXISTING DECK DRAINS	EACH	4	4
X0322194	POLYMER MODIFIED PORTLAND CEMENT MORTAR	SQ FT	40	40
X0322489	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/2"	SQ YD	822	822
X0323491	SLOPE WALL CRACK SEALING	FOOT	29	29
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	54	54
Z0006225	BRIDGE DECK HYDRO-SCARIFICATION 2 1/2"	SQ YD	822	822
Z0015595	DECK DRAIN EXTENSIONS	EACH	5	5
Z0016000	DECK SLAB REPAIR (FULL DEPTH)	SQ YD	20	20
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	1	1
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	1	1
Z0032470	JOINT SEALER	FOOT	76	76
Z0065700	SLOPE WALL REPAIR	SQ YD	15	15

VOID

FILE NAME = c:\pwork\PW100T\WOODSHANKRL\dms91655

USER NAME = woodshankr1
 03-66890-detail.dgn
 PLOT SCALE = 100.0000 / IN.
 PLOT DATE = Mar 25, 2009 - 06:57:27 AM

DESIGNED - RON WOODSHANK
 DRAWN - RON WOODSHANK
 CHECKED -
 DATE -

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
SN 050-0170 (NB)

SCALE: SHEET NO. 2 OF 2 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	(50-7B)I-2	LASALLE	29	4
FED. ROAD DIST. NO. [ILLINOIS]			CONTRACT NO. 66890	