



## DETAILS AT ENTRANCES AND SIDEROADS

TEMP RAMP AT STRUCTURE



## PLAN AT SIDEROADS



## NOTE:

THE COST OF REMOVAL AT EXISTING HMA SIDEROADS LOCATIONS SHALL BE PAID FOR AS HMA SURFACE REMOVAL BUTT-JOINT. SEE SCHEDULE OF QUANTITIES FOR BUTT JOINT TREATMENT AT SIDE ROADS.

THE COST OF REMOVAL AT EXISTING HMA PRIVATE OR COMMERCIAL ENTRANCES LOCATIONS <u>SHALL NOT</u> BE PAID FOR AS HMA SURFACE REMOVAL BUTT-JOINT BUT IT SHALL BE INCLUDED IN THE COST OF THE HMA MATERIALS.

CHIP AND SEAL OR AGGREGATE FOR PRIVATE OR COMMERCIAL ENTRANCES SHALL BE FEATHER TAPERED.

FILE NAME = Typical Section.dgn	USER NAME = lababidism	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		F.A.S SECTION COUNTY TOTAL	SHEET
		DRAWN -	REVISED -		1	2370 (29,32,33,34)RS-3 WOODFORD 56	NO.
	PLOT SCALE = 100.0000 '/ IN.	CHECKED -	REVISED ~		SIDE ROAD AND ENTRANCE DETAILS	CONTRACT NO.	68401
	PLDT DATE = 1/26/2009	DATE -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	ILLINOIS FED. AID PROJECT	30102