

RESURFACING SCHEDULE (MAINLINE PAVEMENT)							
LOCATION STATION TO STATION	HMA SURF REM, BUTT JOINT	HMA SURF REM, VD	BIT (PRIME COAT)	AGG (PRIME COAT)	LVL BINDER MM N50	BND CSE, IL-19.0, N50, VD	HMA SURF CSE, MIX C, N50 1-1/2"
	SQ YD	SQ YD	TON	TON	TON	TON	TON
STA 767+80 TO STA 768+10	73.3		0.03	0.15			6.2
STA 768+10 TO STA 813+19 BK		11022.03	4.19	22.04	466		925.81
STA 810+00 AH TO STA 854+00		10755.56	4.09	21.51	451.73		903.47
STA 854+00 TO STA 857+00		733.3	0.28	1.47	31.10		61.60
STA 857+00 TO STA 859+00		488.9	0.19	0.98	20.7		41.10
STA 859+00 TO STA 860+ 76					18.21		36.14
864+06.50 TO STA 872+00		1866.3	0.71	3.73		803	162.86
STA 872+00 TO STA 879+00		1604.7	0.61	3.21		1105.70	145.6
SUBTOTAL FROM ENTRANCES	538.0		0.20	0.80			
SUBTOTAL FROM BOAT RAMP ACCESS ROAD			7.6			74.00	44
<b>SUBTOTAL MASON COUNTY</b>	<b>611.3</b>	<b>26470.8</b>	<b>17.9</b>	<b>53.9</b>	<b>987.7</b>	<b>1982.2</b>	<b>2326.8</b>
STA 932+00 TO STA 947+00		666.7	0.25	1.33		744.10	67.2
STA 947+00 TO STA 952+70		1326.7	0.50	2.65	41.25	181.80	127.4
STA 952+70 TO STA 953+00	73.3		0.03	0.15			6.2
SUBTOTAL FROM ENTRANCES	512.0		0.20	1.00			
<b>SUBTOTAL CASS COUNTY</b>	<b>585.3</b>	<b>1993.4</b>	<b>1.0</b>	<b>5.1</b>	<b>41.3</b>	<b>925.9</b>	<b>200.8</b>
<b>TOTALS</b>	<b>1197</b>	<b>28464</b>	<b>19</b>	<b>59</b>	<b>1029</b>	<b>2908</b>	<b>2528</b>

HMA BASE COURSE/WIDENING 12"			
LOCATION STATION TO STATION	SUB-BASE GRAN MATERIAL, TY A 12"	HMA BASE COURSE, 12"	HMA BASE COURSE WIDENING, 12"
	SQ YD	SQ YD	SQ YD
STA 857+00 TO STA 872+00	2678.7	989	418
STA 872+00 TO STA 887+00	0	720	179
<b>SUBTOTAL MASON COUNTY</b>	<b>2678.7</b>	<b>1709</b>	<b>597</b>
STA 932+00 TO STA 947+00	0	710	0
STA 947+00 TO STA 952+70	0	233	44
<b>SUBTOTAL CASS COUNTY</b>	<b>0</b>	<b>943</b>	<b>44</b>
<b>TOTALS</b>	<b>2679</b>	<b>2652</b>	<b>641</b>

HMA SHOULDER SCHEDULE			
LOCATION (STATION TO STATION)	HMA SHOULDER 6"	HMA SHOULDER 8"	HMA SHOULDER, VAR. DEPTH
	SQ YD	SQ YD	TON
STA 767+80 TO STA 813+19 BK		4034.7	
STA 810+00 AH TO STA 854+00		3911.1	
STA 854+00 TO STA 854+30	0	14.8	0
STA 854+30 TO STA 857+00	0	389.6	0
STA 857+00 TO STA 872+00	124.4	265.0	149.1
STA 872+00 TO STA 887+00	300.0	533.3	75.8
STA 887+00 TO STA 902+00	0	1383.4	0
STA 902+00 TO STA 907+00	0	248.0	0
<b>SUBTOTAL MASON COUNTY</b>	<b>424.4</b>	<b>10779.9</b>	<b>224.9</b>
STA 917+00 TO STA 932+00	0	1245.3	0
STA 932+00 TO STA 947+00	100.0	1550.0	25.3
STA 947+00 TO STA 952+70	83.3	0	21.1
STA 952+70 TO STA 953+00	0	0	0
<b>SUBTOTAL CASS COUNTY</b>	<b>183.3</b>	<b>2795.3</b>	<b>46.4</b>
<b>TOTAL</b>	<b>608</b>	<b>13575</b>	<b>271</b>

CONCRETE SHOULDER CURB SCHEDULE	
LOCATION (STATION TO STATION)	CONCRETE SHOULDER CURB (5')
	FT
STA 864+36.50 TO STA 864+51.50	15
STA 903+78 TO STA 903+88	10
<b>SUBTOTAL MASON COUNTY</b>	<b>25</b>
STA 922+66 TO STA 922+76	10
<b>SUBTOTAL CASS COUNTY</b>	<b>10</b>
<b>TOTAL</b>	<b>35</b>

LIME MODIFIED SOILS SCHEDULE		
STATION TO STATION LOCATION	PROCESSING MODIFIED SOIL, 12"	LIME
	SQ YD	TON
STA 857+00 TO STA 872+00	77.80	1.56
STA 872+00 TO STA 887+00	4351.50	87.03
STA 887+00 TO STA 902+00	6061.10	121.22
STA 902+00 TO STA 907+00	804.10	16.08
<b>SUBTOTAL MASON COUNTY</b>	<b>11294.50</b>	<b>225.9</b>
STA 907+00 TO STA 917+00	0	0
STA 917+00 TO STA 932+00	4305.90	86.12
STA 932+00 TO STA 947+00	6163.90	123.28
STA 947+00 TO STA 952+70	413.30	8.27
<b>SUBTOTAL CASS COUNTY</b>	<b>10883.10</b>	<b>217.7</b>
<b>TOTALS</b>	<b>22178</b>	<b>443.6</b>

SUB-BASE GRANULAR MATERIAL, TYPE C SCHEDULE		
LOCATION (STATION TO STATION)	SUB-BASE WIDTH	SUB-BASE GRAN MTL TY C, VAR DEPTH
	FT	TON
STA 854+00 TO STA 854+30	0	0.00
STA 854+30 TO STA 857+00	0	0.00
STA 857+00 TO STA 872+00	5.2	19.70
STA 872+00 TO STA 887+00	Varies	389.60
STA 887+00 TO STA 902+00	Varies	573.30
STA 902+00 TO STA 907+00	6.2 ave	87.60
<b>SUBTOTAL MASON COUNTY</b>		<b>1070.20</b>
STA 917+00 TO STA 932+00	7.2 ave	510.60
STA 932+00 TO STA 947+00	Varies	665.90
STA 947+00 TO STA 952+70	Varies	30.00
STA 952+70 TO STA 953+00	0	0.00
<b>SUBTOTAL CASS COUNTY</b>		<b>1206.50</b>
<b>TOTAL</b>		<b>2277</b>

WORK ZONE PAVEMENT MARKING REMOVAL SCHEDULE		
LOCATION STATION TO STATION	LENGTH (FT)	REMOVAL (SQ FT)
SHORT-TERM STA 767+80 TO STA 813+19 AH	4539	150
SHORT-TERM STA 810+00 AH TO STA 854+00	4400	145
SHORT-TERM EDGE LINES STA 856+10 TO STA 907+00 PRIOR TO SURF CSE	5090	135.73
SHORT-TERM SKIP-DASH STA 856+10 TO STA 907+00 PRIOR TO SURF CSE	5090	169.67
<b>SUBTOTAL MASON COUNTY</b>		<b>600.40</b>
SHORT-TERM EDGE LINES STA 907+00 TO STA 953+00 PRIOR TO SURF CSE	4600	122.67
SHORT-TERM SKIP-DASH STA 907+00 TO STA 953+00 PRIOR TO SURF CSE	4600	153.33
<b>SUBTOTAL CASS COUNTY</b>		<b>276.00</b>
<b>TOTAL</b>		<b>876</b>

ACCESS GATE, DOUBLE 30' SCHEDULE	
APPROX LOCATION	ACCESS GATE, DBL 30'
	EACH
STA 6+00 BOAT RAMP ACCESS	1
<b>TOTAL</b>	<b>1</b>

AGGREGATE SHOULDER SCHEDULE		
LOCATION (STATION TO STATION)	AGG SHLD WIDTH	AGG SHLD, TY B, VAR DEPTH
	FT	TON
STA 767+80 TO STA 813+19 BK	3	280.01
STA 810+00 AH TO STA 854+00	3	271.44
STA 854+00 TO STA 854+30	4	3.11
STA 854+30 TO STA 857+00	4	2.99
STA 857+00 TO STA 872+00	4	171.5
STA 872+00 TO STA 887+00	4	227.8
STA 887+00 TO STA 902+00	4	227.8
STA 902+00 TO STA 907+00	4	28.2
<b>SUBTOTAL MASON COUNTY</b>		<b>1212.85</b>
STA 917+00 TO STA 932+00	4	141.8
STA 932+00 TO STA 947+00	4	227.8
STA 947+00 TO STA 952+70	4	86.65
STA 952+70 TO STA 953+00	4	4.55
<b>SUBTOTAL CASS COUNTY</b>		<b>460.8</b>
<b>TOTAL</b>		<b>1675</b>

PAVEMENT REMOVAL SCHEDULE		
STATION	PAVEMENT REMOVAL LENGTH	PAVEMENT REMOVAL
	FT	SQ YD
STA 857+00 TO STA 872+00	122	298.22
STA 875+50 TO STA 880+50	500	611.11
STA 880+50 TO STA 887+00	650	1588.89
STA 887+00 TO STA 902+00	1500	3666.67
STA 902+00 TO STA 906+68	468	1144.00
<b>SUBTOTAL MASON COUNTY</b>		<b>7308.89</b>
STA 917+40 TO STA 929+90	1250	3055.56
STA 936+00 TO STA 941+50	550	1344.44
STA 941+50 TO STA 948+50	700	855.56
<b>SUBTOTAL CASS COUNTY</b>		<b>5255.56</b>
<b>TOTAL</b>		<b>12564</b>

HMA FULL DEPTH PAVEMENT SCHEDULE	
LOCATION STATION TO STATION	HMA FULL DEPTH PAVEMENT, 13-1/2"
	SQ YD
STA 872+00 TO STA 887+00	2329.3
STA 887+00 TO STA 902+00	4183.3
STA 902+00 TO STA 907+00	520.1
<b>SUBTOTAL MASON COUNTY</b>	<b>7032.7</b>
STA 907+00 TO STA 932+00	2606.2
STA 932+00 TO STA 947+00	3346.7
<b>SUBTOTAL CASS COUNTY</b>	<b>5952.9</b>
<b>TOTALS</b>	<b>12986</b>

TEMPORARY RAMP SCHEDULE			
APPROX STATION	WIDTH	APPROXIMATE LOCATION	TEMP RAMP
	FT		SQ YD
854+00	22	BEGINNING OF JOB	12.22
859+00	34	WOLF LAKE N. BR APPROACH	132.22
859+00	34	BR. OMISSION	75.56
865+00	34	BR. OMISSION	75.56
898+00	100	BOAT RAMP ACCESS RD	111.11
903+85	36	BR. OMISSION	80.00
<b>SUBTOTAL MASON COUNTY</b>			<b>486.67</b>
922+85	36	BR. OMISSION	80.00
953+00	22	END OF JOB	12.22
<b>SUBTOTAL CASS COUNTY</b>			<b>92.22</b>
<b>TOTAL</b>			<b>579</b>