

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL		
			90% FEDERAL; 10% STATE CONSTRUCTION TYPE CODE SFTY-2A		
			JOHNSON	PULASKI	
			SN 044-0031	SN 077-0027	
QUANTITY	QUANTITY	QUANTITY			
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	193	193	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	252		252
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	188	188	
40600990	TEMPORARY RAMP	SQ YD	42	42	
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	61	29	32
42001300	PROTECTIVE COAT	SQ YD	2708	1552	1156
50102400	CONCRETE REMOVAL	CU YD	32.7	13.3	19.4
50157300	PROTECTIVE SHIELD	SQ YD	442	360	482
50300100	FLOOR DRAINS	EACH	20		20
50300255	CONCRETE SUPERSTRUCTURE	CU YD	35	14.2	20.8
50300260	BRIDGE DECK GROOVING	SQ YD	2462	1444	1018
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	4270	2350	1920
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	30	12	18
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4190	1640	2550
50800515	BAR SPLICERS	EACH	20	20	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	115	115	
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	12	12	
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	18		18
52100520	ANCHOR BOLTS, 1"	EACH	84	48	36
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	6.7		6.7
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4		4
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1		1
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1		1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	2	2	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70106700	TEMPORARY RUMBLE STRIP	EACH	3	3	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	14	6	8
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	160	90	70
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2780	1304	1476

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL		
			90% FEDERAL; 10% STATE CONSTRUCTION TYPE CODE SFTY-2A		
			JOHNSON	PULASKI	
			SN 044-0031	SN 077-0027	
QUANTITY	QUANTITY	QUANTITY			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	980	465	515
70400100	TEMPORARY CONCRETE BARRIER	FOOT	575	575	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	550	550	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2780	1304	1476
78300100	PAVEMENT MARKING REMOVAL	SQ FT	497	497	
* 86200300	UNINTERRUPTIBLE POWER SUPPLY, EXTENDED	EACH	1	1	
X0301245	SHOULDER REMOVAL	SQ YD	193	193	
X0301424	SILICONE JOINT SEALER	FOOT	127		127
X0320887	POLYMER CONCRETE	CU FT	9.9		9.9
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	235	235	
XZ193500	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4"	SQ YD	2643	1516	1127
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	2643	1516	1127
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	36	2	34
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	

*Specialty Items