

# SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	RURAL - PULASKI COUNTY	
		100% STATE	
		UNIT	TOTAL QUANTITIES
		1000	
20900310	POROUS GRANULAR BACKFILL	TON	806
25000200	SEEDING, CLASS 2	ACRE	0.05
25000350	SEEDING, CLASS 7	ACRE	0.05
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	5
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	5
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	5
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.1
25100115	MULCH, METHOD 2	ACRE	0.05
28000500	INLET AND PIPE PROTECTION	EACH	1
28100807	STONE <sup>DUMPED</sup> RIPRAP, CLASS A4	TON	119
44000100	PAVEMENT REMOVAL	SQ YD	128
44004250	PAVED SHOULDER REMOVAL	SQ YD	40
44201349	CLASS C PATCHES, TYPE I, 10 INCH	SQ YD	171
44213200	SAW CUTS	FOOT	64
48101200	AGGREGATE SHOULDERS, TYPE B	TON	8
50105200	REMOVE EXISTING CULVERTS	EACH	1
542A2773	PIPE CULVERTS, CLASS A, TYPE 4 48"	FOOT	75
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	1
54215448	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 48"	EACH	1
60801048	FLAP GATE 48"	EACH	1
* 63300115	REMOVAL AND REINSTALLATION OF EXISTING STEEL PLATE BEAM GUARD RAIL, SINGLE RAIL	FOOT	62.5
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70101835	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1.5
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	156
Z0075310	TIE BARS 3/4"	EACH	46

*\*Specialty Items*

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2937	116(1-1)	PULASKI	7	3
CULVERT REPLACEMENT				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				